

## SUMMARY OF QUANTITIES

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	35RS-5,36RS-8	TAZEWELL	90	5
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ALWAYS	FED. AID PROJECT	

\*6717 (BUS 24) &amp; 6713 (IL 8)

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000 100% STATE	BRIDGE X241-2A 100% STATE	CITY 1000-1A 100%		
44201394	CLASS C PATCHES, TYPE III, 13 INCH	SQ YD	122	122				
44201396	CLASS C PATCHES, TYPE IV, 13 INCH	SQ YD	163	163				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	15	15				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	61	61				
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	65	65				
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	1117	1117				
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	159	159				
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SQ YD	580	580				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,220	1,220				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1574	1574				
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2250	2250				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6				
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6	6				
63200310	GUARD RAIL REMOVAL	FOOT	2806	2806				
63500105	DELINEATORS	EACH	35	35				
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	5	5				
66700605	PERMANENT SURVEY TIES	EACH	4	4				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				

\*SPECIALTY ITEM