

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
35RS-5,36RS-8	TAZEWELL	90	37	
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*6717 (BUS 24) & 6713 (IL 8)				

RESURFACING - RAMPS (SHOULDERS)

	AREA	HMA SURF REM (BT JT)	HMA SURF REM 3/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURF CSE, MIX C, N50, 1.5"
	SQ FT	SQ YD	SQ YD	TON	TON	TON
RAMP A - SHOULDERS						
RT. STA. 0+00 - 17+30	10396.0		1155.1	0.46	2.3	97.0
RT. STA. 17+30 - 17+73	280.6	31.2		0.01	0.1	2.6
LT. STA. 0+00 - 8+00	3200.0		355.6	0.14	0.7	29.9
LT. STA. 9+97.60 - 17+30	2968.2		329.8	0.13	0.7	27.7
LT. STA. 17+30 - 17+73	88.5	9.8		0.01	0.0	0.8
GORE	4872.2		541.4	0.22	1.1	45.5
RAMP B - SHOULDERS						
RT. STA. 2+00 - 9+23	4329.2		481.0	0.19	1.0	40.4
RT. STA. 9+23 - 9+59	180.7	20.1		0.01	0.0	1.7
BRIDGE OMISSION						
RT. STA. 12+35.90 - 12+73	244.1	27.1		0.01	0.1	2.3
RT. STA. 12+73 - 23+31	6363.9		707.1	0.28	1.4	59.4
RT. STA. 23+31 - 23+61	180.0	20.0		0.01	0.0	1.7
LT. STA. 0+00 - 9+23	3734.0		414.9	0.17	0.8	34.9
LT. STA. 9+23 - 9+63	142.6	15.8		0.01	0.0	1.3
BRIDGE OMISSION						
LT. STA. 12+52.04 - 12+86.5	129.1	14.3		0.01	0.0	1.2
LT. STA. 12+86.57 - 23+31	4107.5		456.4	0.18	0.9	38.3
LT. STA. 23+31 - 23+61	120.0	13.3		0.01	0.0	1.1
RAMP C - SHOULDERS						
RT. STA. 12+93.62 - 13+23.6	179.4	19.9		0.01	0.0	1.7
RT. STA. 13+23.62 - 13+53.6	180.0		20.0	0.01	0.1	1.7
LT. STA. 12+93.62 - 13+23.6	120.0	13.3		0.01	0.0	1.1
LT. STA. 13+23.62 - 13+53.6	120.0		13.3	0.00	0.1	1.1
GORE	417.5		46.4	0.02	0.1	3.9
RAMP D - SHOULDERS						
RT. STA. 0+10 - 0+40	180.0	20.0		0.01	0.1	1.7
RT. STA. 0+40 - 2+12.07	1118.0		124.2	0.05	0.2	10.4
LT. STA. 0+10 - 0+40	120.0	13.3		0.00	0.1	1.1
LT. STA. 0+40 - 5+22.63	1922.3		213.6	0.09	0.4	17.9
TOTALS		218.1	4858.8	2.05	10.2	426.4

AGGREGATE (EROSION CONTROL)	
LOCATION	TON
RAMP A	
RT 2+56.50 - 3+06.50	1.3
LT 1+26.51 - 3+01.51	4.4
RAMP B	
RT 6+44.50 - 9+72	8.3
RT 12+32 - 20+57.50	20.9
LT 7+17 - 9+82	6.7
LT 12+56 - 13+31.50	1.9
IL 8	
RT 281+28 - 285+28	25.3
RT 290+87.50 - 293+75	18.2
TOTALS	87

PLOT DATE = 4/1/2007
 FILE NAME = c:\pwworkspace\bus24\external\plan.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = kllm-nk

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. DATE: HORIZ.

DRAWN BY CHECKED BY