

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	35RS-5,3GRS-8	TAZEWELL	90	38
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*6717 (BUS 24) & 6713 (IL 8)				

RESURFACING - BUS U.S. ROUTE 24 (MAINLINE)

	AREA	HMA SURF REM 1-1/2"	HMA SURF REM 2-1/4"	BIT MAT'S (PRIME COAT)		AGG (PRIME COAT)		LEVEL BINDER (MM), N50	POLY, HMA SURF CSE, MIX D, N70
				MILLED SURFACE	NEW BINDER	MILLED SURFACE	NEW BINDER		
	SQ FT	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON
EASTBOUND									
STA. 428+84.25 - 431+34.2	3500.0	388.9		0.16	0.05	0.8	0.4	16.3	32.7
STA. 431+34.25 - 470+50.7	93996.0	10444.0		4.18	1.25	20.9	10.4	438.6	877.3
STA. 470+50.75 - 470+65.7	360.0		40.0	0.02	0.01	0.1	0.1	1.7	3.4
STA. 470+65.75 - 486+17.1	37233.6		4137.1	1.65	0.50	8.3	4.1	173.8	347.5
STA. 486+17.15 - 486+32.1	360.0		40.0	0.02	0.01	0.1	0.1	1.7	3.4
STA. 486+32.15 - 494+65.6	20004.7	2222.7		0.89		4.4			186.7
TURN LANES									
STA. 456+69.01 - 463+00	6092.7	677.0		0.27	0.08	1.4	0.7	28.4	56.9
STA. 456+89.68 - 463+79.9	6329.0	703.2		0.28	0.08	1.4	0.7	29.5	59.1
STA. 488+81.28 - 494+65.6	7116.9	790.8		0.32		1.6			66.4
MEDIAN									
STA. 494+00 - 494+76.68	467.5	51.9		0.02		0.1			4.4
WESTBOUND									
STA. 449+26.41 - 474+98.3	62085.6	6898.4		2.76	0.83	13.8	6.9	289.7	579.5
STA. 474+98.31 - 475+28.3	360.0		40.0	0.02	0.01	0.1	0	1.7	3.4
STA. 475+28.31 - 490+63.1	36835.0		4092.8	1.64	0.49	8.2	4.1	171.9	343.8
STA. 490+63.10 - 490+93.1	360.0		40.0	0.02	0.01	0.1	0.1	1.7	3.4
STA. 490+93.10 - 494+65.6	8343.4	927		0.37		1.9			77.9
CROSSOVER									
STA. 461+00 - 463+25	2951.4	327.9		0.13	0.04	0.7	0.3	13.8	27.5
TURN LANES									
460+70.13 - 467+52.34	6319.5	702.2		0.28	0.09	1.4	0.7	29.5	59.0
461+20 - 467+73.01	6075.6	675.1		0.27	0.08	1.4	0.7	28.4	56.7
491+79.59 - 494+65.68	3253.9	361.5		0.14		0.7			30.4
MEDIAN									
494+00 - 494+65.68	485.9	54.0		0.02		0.1			4.5
TOTALS		25224.6	8389.9	13.46	3.53	67.5	29.3	1226.7	2823.9

PLOT DATE = 4/1/2007
 FILE NAME = c:\pva\resur\bus24\connut-plenudgn
 PLOT SCALE = 100.0000' / IN.
 USER NAME = h1jme-ka

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES
OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY