

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	35RS-5,36RS-8	TAZEWELL	90	39
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*6717 (BUS 24) & 6713 (IL 8)				

RESURFACING - BUS U.S. ROUTE 24 (SHOULDERS)

	AREA	HMA SURF REMOVAL BT JT	HMA SURF REMOVAL 3/4"	HMA SURF REMOVAL 1-1/2"	BIT MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURF CSE, MIX C, N50, 1.5"
	SQ FT	SQ YD	SQ YD	SQ YD	TON	TON	TON
EAST BOUND (OUTSIDE)							
426+29.46 - 428+84.25	1528.7		169.9		0.07	0.3	14.3
428+84.25 - 431+34.25	2000.0		222.2		0.09	0.4	18.7
431+34.25 - 461+24.68	27984.3		3109.4		1.24	6.2	261.2
463+16.34 - 470+50.75	7186.3		798.5		0.32	1.6	67.1
470+50.75 - 471+62.35	1116.0			124.0	0.05	0.2	10.4
471+62.35 - 471+77.35	150.0	16.7			0	0.0	1.4
486+17.15 - 486+32.15	150.0	16.7			0.01	0.0	1.4
486+32.15 - 494+65.68	5078.5			564.3	0.23	1.1	47.4
EAST BOUND (INSIDE)							
426+29.46 - 428+18.95	758.0		84.2		0.03	0.2	7.1
431+34.25 - 461+65.95	12126.8		1347.4		0.54	2.7	113.2
462+73.28 - 470+50.75	3109.9		345.5		0.14	0.7	29.0
470+50.75 - 470+65.75	60.0	6.7			0.01	0.0	0.6
486+13.38 - 486+28.38	60.0	6.7			0.00	0.0	0.6
486+28.38 - 494+65.68	3349.2			372.1	0.15	0.7	31.3
TOTALS		46.8	6077.1	1060.4	2.88	14.1	603.7

TEMPORARY RAMPS	
LOCATION	SQ YD
RAMP A	
RT 17+73	8.9
RAMP B	
23+61	8.9
12+74.5	8.9
9+55.35	8.9
RAMP C	
12+93.62	8.9
RAMP D	
0+10	8.9
SPRING CREEK RD (N)	13.3
SPRING CREEK RD (S)	13.3
IL 8	
191+00	33.3
322+28	46.1
LEGION RD	13.3
HIGHWOODS RD.	13.3
WESTLAKE RD.	16.7
K MART ENTR.	17.8
CUMMING LN. (N)	23.6
CHERRY TREE ENT.	41.7
COMMERCIAL ENT.	27.8
COMMERCIAL ENT.	19.4
CUMMING LN.(S)	20.0
CENTENNIAL (S)	62.2
FREEDOM PKY. (N)	62.2
SUMMIT DR. (N)	18.9
SUMMIT DR. (S)	25.6
SCHOOL ST. (N)	24.4
SCHOOL ST. (S)	19.5
TOTALS	566

PLOT DATE = 4/11/2007
 FILE NAME = c:\pwworkspace\bus24\creswell\plan.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = h1jmarck

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. DATE
 HORIZ.

DRAWN BY
 CHECKED BY