

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	35RS-5,36RS-8	TAZEWELL	90	42
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*6717 (BUS 24) & 6713 (IL 8)				

RESURFACING - SIDEROADS

	AREA	HMA SURF REMOVAL (BT JT)	HMA SURF REMOVAL 1-1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HMA SURF	POLY HMA SURF CSE, MIX D, N70, 1-1/2"	HMA SURF CSE, MIX C, N50, 1.5"
	SQ FT	SQ YD	SQ YD	TON	TON	TON	TON	TON
LEGION RD	2580.0	85.1	201.6	0.11	0.6	24.1		
RT SHOULDER	541.6	13.3	46.8	0.02	0.1			5.0
LT SHOULDER	400.5	13.6	30.9	0.02	0.1			3.7
HIGHWOODS RD	2428.1	85.1	184.7	0.10	0.6	22.7		
RT SHOULDER	346.4	13.6	24.9	0.02	0.1			3.2
LT SHOULDER	465.6	13.3	38.4	0.03	0.1			4.3
KMART ENTR.	3188.7	106.4	247.9	0.14	0.5	29.8		
WESTLAKE RD	2776.0	108.9	199.6	0.12	0.6	25.9		
RT SHOULDER	466.0	13.4	38.4	0.03	0.1			4.3
LT SHOULDER	364.4	14.0	26.5	0.02	0.1			3.4
CUMMINGS (N)	7595.4	144.2	2513.7	1.07	5.3		223.3	
CUMMINGS (S)	7825.2	125.2	744.2	0.35	1.7	73.0		
ENTRANCES/MAILBOXES	6312			0.14	1.40	35		
TOTALS		736	4298	2.17	11	211	223	24

RESURFACING - IL 8 (SHOULDERS)

	AREA	HMA SURF REMOVAL BT JT	HMA SURF REMOVAL 1-1/2"	BITUMINOUS MATERIALS (PRIME)	AGGREGATE (PRIME)	HMA SURF CSE, MIX C, N50, 1.5"
	SQ FT	SQ YD	SQ YD	TON	TON	TON
201+00 - 222+00	8460			0.19	1.9	118.4
222+00 - 228+00	2250			0.05	0.5	31.5
228+00 - 232+00	483			0.01	0.11	6.8
232+00 - 240+00	2400			0.05	0.53	33.6
240+00 - 260+00	1005			0.02	0.22	14.1
(RT SIDE)						
260+00 - 271+58.10	9225.9		1025.1	0.41	2.1	86.1
272+93.58 - 302+89.66	27426.4		3047.4	1.22	6.1	256.0
304+29.66 - 315+90	9304.3		1033.8	0.41	2.1	86.8
318+39.02 - 321+98	3538.1		393.1	0.16	0.8	33.0
321+98 - 322+28	251.9	28.0		0.01	0.1	2.4
(LT SIDE)						
260+00 - 283+38.86	15434.2		1714.9	0.69	3.4	144.1
286+54 - 296+11.24	7504.9		833.9	0.33	1.7	70.0
297+25.58 - 311+09.03	12333.1		1370.3	0.55	2.7	115.1
312+15 - 316+01.69	4362.9		484.8	0.19	1.0	40.7
318+25 - 321+98	1612.6		179.2	0.07	0.4	15.1
321+98 - 322+28	253.9	28.2		0.01	0.1	2.4
TOTALS		56.2	10082.5	4.05	20.5	851.7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. DATE

DRAWN BY CHECKED BY