CONTRACT NO. 68351

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	35RS-5,36RS-8	TAZEWELL	90	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*6717 (BUS 24) & 6713 (IL 8)

EPOXY & TEMPORARY PAVEMENT MARKING

LOCATION	LETTERS & SYMBOLS SQ FT
BUS 24 @ SPRING CREEK RD	
6 RT TURNS	93.6
6 LT TURNS	93.6
BUS 24 @ IL 8	
3 RT TURNS	46.8
6 LT TURNS	93.6
IL 8 STA 191+00 - 229+90	
2 RT TURNS	31.2
30 LT TURNS	468.0
SUMMIT DR (1 RT TURN)	15.6
SCHOOL ST (1 RT TURN)	15.6
IL 8 LEGION RD	
2 RT TURNS	31.2
2 LT TURNS	31.2
IL 8 @ BUS 24	
3 LT TURNS	46.8
3 RT TURNS	46.8
IL 8 @ HIGHWOODS RD	
3 RT TURNS	46.8
3 LT TURNS	46.8
IL 8 @ WESTLAKE RD	
4 RT TURNS	62.4
3 LT TURNS	46.8
IL 8 @ CUMMINGS	
7 RT TURNS	109.2
13 LT TURNS	202.8
3 THRU	34.5
5 COMBINATION	104.0
TOTALS	1667

EPOXY & TEMPORARY PAVEMENT MARKING - LINE 12"

LOCATION	FOOT
GORE @ RAMPS C/D	29.3
GORE @ RAMPS A/B	167.8
SPRING CREEK RD. (N)	39.0
SPRING CREEK RD. (S)	38.5
EB BUS 24 @ IL 8	245.3
WB BUS 24 @ IL 8	250.9
IL 8 STA. 191+00 - 263+20	1133
SCHOOL ST NW QUADRANT	27
IL 8 STA. 263+20 - 266+19.70	111.2
IL 8 STA. 265+69.57 - 271+51	221.6
WESTLAKE RD.	31.4
CUMMINGS LANE SW QUADRANT	57.8
CUMMINGS LANE SE QUADRANT	51.3
CUMMINGS LANE NE QUADRANT	76.5
CUMMINGS LANE NW QUADRANT	63.3
CUMMINGS LANE (N)	9.4
IL 8 STA. 313+98.50 - 316+70	43.0
IL 8 STA. 317+54.64 - 319+58.09	30.7
TOTALS	2627

EPOXY & TEMPORARY PAVEMENT MARKING - LINE 24"

LOCATION	FOOT
BUS 24 EB @ CENTENNIAL DR.	24
BUS 24 WB @ CENTENNIAL DR.	24
IL 8 & SUMMIT DR	127
IL 8 & SCHOOL ST	138
LEGION RD	12
BUS 24 EB @ IL8	24
IL 8 EB @ BUS 24	36
IL 8 WB @ BUS 24	24
HIGHWOODS RD	12
WESTLAKE RD	12
EB IL 8 @ CUMMINGS	38
WB IL 8 @ CUMMINGS	38
SB CUMMINGS	60.5
NB CUMMINGS	58.6
SPRING CREEK RD. (N)	12
SPRING CREEK RD. (S)	12
TOTALS	652

PREFORMED PLASTIC (TY B) & TEMORARY PAVEMENT MARK - LINE 6"

LOCATION	SKIP-DASH (WHITE) FOOT
RAMP D	
STA. 3+50 - 5+22.63	50
BUS 24 (EB)	
STA. 431+34.25 - 494+65.6	1590
BUS 24 (EB)	
445+43 - 491+76.60	1160
IL 8 (EB)	
STA. 266+20 - 322+28	1410
IL 8 (WB)	
STA. 271+51 - 322+28	1270
TOTALS	5480

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 4/4/2007
FILE NAME = c:\projects\bus24\consult_plan.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = hilmanwk