

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44-45IRS-5, 46-1IRS-7, 45-(RB, RB-2, BR))	PEORIA	82	2
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

COMMITMENTS

Commitments are not to be altered without the written consent of all parties to which the commitment was made.

Permanent Survey Marker at Sta. 310+34.94 is to be salvaged and is to remain undisturbed and unaltered. See Reference Points Detail Sheet for exact location.

DISTRICT CADD STANDARDS

- 406101-D4 Butt Joints
- 440001-D4 Bituminous Surface Removal (Cold Milling)
- 630101-D4 Guardrail Erosion Control Treatments

GENERAL NOTES

PLAN ELEVATIONS - U.S.G.S. MEAN SEA LEVEL DATUM

All elevations shown on the plans are established from U.S.G.S. means sea level datum.

PROPERTY OWNER ACCESS REQUIREMENT

Access must be maintained to all existing properties during construction per Article 107.09 unless arrangement made in writing by the Contractor with the property owners with a copy to the Engineer to short-term closures.

WINTER SHUTDOWN RESTRICTIONS ON COLD-MILLED PROJECTS

Prior to winter shutdown the following steps shall be taken

- All cold milled surface shall be overlaid
- All lanes shall be reopened to traffic
- Manholes, where applicable, shall be adjusted to the elevation of the binder course/leveling binder to ease in plowing snow, and readjusted to finished grade in the Spring. The initial manhole adjustment will be paid for at the contract unit price and any re-adjustment, as directed by the Engineer, will be paid for in accordance with Article 109.04.
- Temporary or permanent pavement marking shall be placed as applicable

CRITICAL PATH WORK SCHEDULE REQUIREMENT

The Contractor will submit to the Engineer a satisfactory progress schedule and critical path schedule which shall show the proposed sequence of work at the time of the pre-construction conference.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- BDE Form 2289 (Environmental Survey Request)
- A location map showing the size limits and location of the use area
- Signed property owner agreement form
- Color photographs depicting the use area

Please note that a minimum of two weeks shall be allowed for the District to obtain in the required environmental clearances.

BRIDGE OVERLAY NOTIFICATION

After placement of the bridge deck overlay, the Resident Engineer shall notify the District Bridge Maintenance Engineer of the "as constructed" milling depth and overlay thickness for updating the Illinois Highway Information System.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		GENERAL NOTES US 24 (FAP 317) KINGSTON MINES DRAWN BY CHECKED BY
DATE		