

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	44-45IRS-5, 46-1IRS-7, 45-1RB, RB-2, BR1	PEORIA		4
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES					80% FEDERAL FUNDING / 20% STATE FUNDING			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN				
				INTERSTATE ROADWAY	ROADWAY / STRUCTURES 072-0008	BRIDGE S.N. 072-0136	BRIDGE S.N. 072-0010	
				1000	SFTY - 2A	X081 - 2A	SFTY - 2A	
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	425			355	70	
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	2,667	2,667				
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	139.4	139.4				
40600300	AGGREGATE (PRIME COAT)	TON	594	594				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,400	4,400				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	313	313				
40600990	TEMPORARY RAMP	SQ YD	1,495	1,495				
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	141	40			101	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	16,466	16,466				
42001200	PAVEMENT FABRIC	SQ YD	404	404				
42001300	PROTECTIVE COAT	SQ YD	756			578	178	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	31,990	31,990				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	235,057	235,057				
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	104	104				
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,667	2,667				
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	2,227	2,227				
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	255	255				
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	150	150				

SUMMARY OF QUANTITIES