

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	144-45(RS-5, 446-1(RS-7, 45-(RB, RB-2, BR))	PEORIA	82	11
FED. ROAD DIST. NO. - ILLINOIS			FED. AID PROJECT	

SAW CUTS							
LOCATION	PATCH UNIT	TYPE II		TYPE III		TYPE IV	
		NO. OF PATCHES	LINEAR FT.	NO. OF PATCHES	LINEAR FT.	NO. OF PATCHES	LINEAR FT.
<b>EASTBOUND LANES</b>							
STA. 289+72 TO STA. 335+70	1	30	1644	1	84	2	222
STA. 335+70 TO STA. 410+22	2	28	1536	3	258		
STA. 410+22 TO STA. 519+83	3	77	4128	1	81	3	294
STA. 519+83 TO STA. 607+38	4	88	4806	7	510		
<b>WESTBOUND LANES</b>							
STA. 289+72 TO STA. 335+70	1	4	216				
STA. 335+70 TO STA. 410+22	2	12	648				
STA. 410+22 TO STA. 519+83	3	25	1374	2	144		
STA. 519+83 TO STA. 607+38	4	2	108				
<b>SUB-TOTAL</b>			14460		1077		516
<b>ADD 15% FOR WINTER BREAKUP</b>							
<b>TOTAL PER TYPE</b>		266	14,460	14	1,077	5	516
				<b>GRAND TOTAL</b>		16,053	

AGGREGATE SHOULDERS, TYPE B	
LOCATION	TON
<b>EASTBOUND</b>	
WHEELER ROAD	10
POWEL ROAD	10
WEST FIRST STREET	10
TERMINAL ROAD	10
JACKSON STREET	10
PEARL STREET	10
RT & LT STA. 470+00 TO STA. 505+82	136
RT & LT STA. 535+53 TO 559+00	89.1
<b>WESTBOUND</b>	
PRIVATE ENTRANCE STA. 310+00	6
PRIVATE ENTRANCE STA. 318+77	6
PRIVATE ENTRANCE STA. 329+90	6
POWELL ROAD	10
WEST FIRST STREET	10
JACKSON STREET	10
RT & LT STA. 467+75 TO STA. 505+82	144.5
RT & LT STA. 535+53 TO 559+00	89.1
<b>TOTAL</b>	
	567

CLASS B PATCH - 15 INCHES								PAVEMENT FABRIC	PATCHING REINFORCEMENT	DOWEL BARS
LOCATION	PATCH UNIT	TYPE II		TYPE III		TYPE IV				
		NO. OF PATCHES	SQ YDS	NO. OF PATCHES	SQ YDS	NO. OF PATCHES	SQ YDS	SQ YD	SQ YD	EACH
<b>EASTBOUND LANES</b>										
STA. 289+72 TO STA. 335+70	1	30	250.8	1	21.3	2	66.7	88	88	660
STA. 335+70 TO STA. 410+22	2	28	234.7	3	66.7			66.7	66.7	620
STA. 410+22 TO STA. 519+83	3	79	677.4	1	20	3	82.7	102.7	102.7	1636
STA. 519+83 TO STA. 607+38	4	88	728.1	7	114.7			114.7	114.7	1900
<b>WESTBOUND LANES</b>										
STA. 289+72 TO STA. 335+70	1	4	32					0	0	80
STA. 335+70 TO STA. 410+22	2	12	96					0	0	240
STA. 410+22 TO STA. 519+83	3	23	194.6	2	32			32	32	540
STA. 519+83 TO STA. 607+38	4	2	16					0	0	40
<b>SUB-TOTAL</b>			2226.6		254.7		149.4	404.1	404.1	5716
<b>ADD 15% FOR WINTER BREAKUP</b>										
<b>TOTAL PER TYPE</b>		266	2229.6	14	254.7	5	149.4	404.1	404.1	5716

SCHEDULE OF QUANTITIES