

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44-45)RS-5, (46-1)RS-7, 45-1RB, RB-2, BR11	PEORIA	82	12
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

PCC SURFACE REMOVAL (COLD MILLING) 2 1/4"	
LOCATION	SQ. YD
FACTORY ROAD	1242
<b>TOTAL</b>	<b>1,242</b>

PCC SURFACE REMOVAL - BUTT JOINTS	
LOCATION	SQ. YD
FACTORY ROAD	
SW ENTRANCE TO CAT	91.7
SE ENTRANCE TO LONZA	90
MAPLETON FACTORY ENTRANCE	131.7
<b>TOTAL</b>	<b>313</b>

REMOVAL & REPLACEMENT OF SPBGR, RAIL ELEMENT	
LOCATION	FEET
EB STA. 297+22	25
EB STA. 296+75	25
WB STA. 339+80	25
EB STA. 376+00	50
EB STA. 416+75	25
EB STA. 502+00	38
EB STA. 531+80	25
<b>TOTAL</b>	<b>213</b>

TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	EACH
<b>EAST BOUND LANES</b>	
STA. 338+89 (SN. 072-0010)	1
STA. 413+70 (SN. 072-0009)	2
STA. 497+51 (SN. 072-0008)	2
<b>WEST BOUND LANES</b>	
STA. 336+86 (SN. 072-0010)	1
STA. 410+22 (SN. 072-0009)	2
STA. 496+22 (SN. 072-0136)	2
<b>TOTAL</b>	<b>10</b>

ADJUST EXISTING GUARD RAIL	
LOCATION	FEET
<b>EASTBOUND LANES</b>	
STA. 293+00 - STA. 302+25	858
STA. 338+89 - STA. 340+26	137
STA. 413+70 - STA. 421+67	797
STA. 497+51 - STA. 505+26 (OUTSIDE SHLD) (LITTLE LAMARSH CR)	775
STA. 497+51 - STA. 498+36 (INSIDE SHLD) (LITTLE LAMARSH CR)	85
<b>WESTBOUND LANES</b>	
STA. 338+89 - STA. 340+64	175
STA. 413+70 - STA. 425+26	1,156
STA. 494+49 - STA. 496+26 (OUTSIDE SHLD) (LITTLE LAMARSH CR)	177
STA. 494+69 - STA. 496+26 (INSIDE SHLD) (LITTLE LAMARSH CR)	157
<b>TOTAL</b>	<b>4,317</b>

VERTICAL ADJUSTMENT OF TRAFFIC BARRIER TERMINAL TYPE 2	
LOCATION	EACH
WESTBOUND STA. 340+64	1
WESTBOUND STA. 425+26	1
<b>TOTAL</b>	<b>2</b>

VERTICAL ADJUSTMENT OF TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	
LOCATION	EACH
EASTBOUND STA. 421+67 (LIT LAMARSH CR)	1
EASTBOUND STA. 498+36 (LIT LAMARSH CR)	1
WESTBOUND STA. 494+49 (LIT LAMARSH CR)	1
WESTBOUND STA. 494+69 (LIT LAMARSH CR)	1
<b>TOTAL</b>	<b>4</b>

SCHEDULE OF QUANTITIES