

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44-45RS-5, 46-1RS-7, 45-1RB, RB-2, BR1)	PEORIA	82	15
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	BRIDGE DECK WEARING SURFACE REMOVAL	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "D", N50	WATER PROOFING MEMBRANE (SPECIAL)	DECK SLAB REPAIR (FULL DEPTH)	DECK SLAB REPAIR (PARTIAL)
	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ YD
EB STA. 336+86 - 338+89 LA MARSH CREEK (SN 072-0010)	1026	0.4	2.1	101	1026	31.0	123.1
EB STA. 496+26 - 497+51 LITTLE LAMARSH CREEK (SN 072-0008)	569	0.2	1.1	40	569	17.0	68.3
TOTALS	1595	0.6	3.2	141	1595	48.0	191.4

SHOULDER RUMBLE STRIPS	
LOCATION	FEET
EASTBOUND LANES OUTSIDE SHOULDER	
STA. 289+72 TO STA. 336+86	4332
STA. 338+89 TO 410+22	6505
STA. 413+70 TO STA. 496+26	6749
STA. 497+51 TO STA. 505+82	831
STA. 526+41 TO 607+38	7895
EASTBOUND LANES INSIDE SHOULDER	
STA. 289+72 TO STA. 336+86	3837
STA. 338+89 TO 410+22	6713
STA. 413+70 TO STA. 492+38	6697
STA. 497+51 TO 589+95	8364
WESTBOUND LANES OUTSIDE SHOULDER	
STA. 289+72 TO 336+86	4032
STA. 338+89 TO 410+22	6960
STA. 413+70 TO STA. 492+38	7609
STA. 497+51 TO 607+38	10885
WESTBOUND LANES INSIDE SHOULDER	
STA. 289+72 TO STA. 336+86	3939
STA. 338+89 TO 410+22	6730
STA. 413+70 TO STA. 496+26	7009
STA. 497+51 TO STA. 519+45	1149
STA. 526+41 TO STA. 559+00	2802
STA. 565+63 TO 579+26	1303
TOTAL	104,341

PERFORMED PLASTIC PAVEMENT MARKING TY. A LINE 6"	
LOCATION	UNIT
EASTBOUND CENTERLINE SKIP	
STA. 289+72 TO STA. 607+38	7810
WESTBOUND CENTERLINE SKIP	
STA. 289+72 TO STA. 607+38	7810
TOTAL	15,620

SCHEDULE OF QUANTITIES