CONTRACT NO. 68456

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44,45)RS-5, (46-1)RS-7, 45-(RB,RB-2,BR)I	PEORIA	82	18
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	HOT-MIX ASPHALT SURFACE REM. BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REM. 2.25 IN	HOT-MIX ASPHALT SURFACE REM. 0.5 IN	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	POLYMERIZED LEVEL BINDER (MACHINE METHOD), N50	POLYMERIZED HMA SURFACE CSE MIX "D", N70	HOT-MIX ASPHALT SHOULDERS			
												LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD	TON	SQ YD	TON
STA. 475 + 17 TO 492 + 38	24.00	1721.00	4589.33				4589.33	2.39	9.18	192.75	385.50				
STA. 492 + 38 TO 496 + 26	24.00	388.00	1034.67	136.67	68.50		898.00	0.54	2.07	43.46	86.91				
BRIDGE OMISSION															
STA. 497 + 51 TO 505 + 82	24.00	831.00	2216.00	136.67	68.50		2079.33	1.15	4.43	93.07	186.14				
STA. 505 + 82 TO 519 + 45	24.00	1363.00	3634.67			3634.67		1.89	7.27	152.66	305.31				
STA. 519 + 45 TO 521 + 41	24.00	196.00	522.67			522.67		0.27	1.05	21.95	43.90				
STA. 521 + 41 TO 526 + 41	24.00	500.00	1333.33			1333.33		0.69	2.67	56.00	112.00				
STA. 526 + 41 TO 535 + 53	24.00	912.00	2432.00			2432.00		1.26	4.86	102.14	204.29				
STA. 535 + 53 TO 538 + 71	24.00	318.45	849.20				849.20	0.44	1.70	35.67	71.33				
STA. 538 + 70 TO 559 + 00	24.00	2030.48	5414.61				5414.61	2.82	10.83	227.41	454.83				
STA. 559 + 00 TO 565 + 63	24.00	663.00	1768.00			1768.00		0.92	3.54	74.26	148.51				
STA. 565 + 63 TO 572 + 25	24.00	662.00	1765.33			1765.33		0.92	3.53	74.14	148.29				
STA. 572 + 25 TO 579 + 26	24.00	701.00	1869.33			1869.33		0.97	3.74	78.51	157.02				
STA. 579 + 26 TO 589 + 95	24.00	1069.00	2850.67			2850.67		1.48	5.70	119.73	239.46				
STA. 589 + 95 TO 590 + 94	24.00	99.00	264.00			264.00		0.14	0.53	11.09	22.18				
STA. 590 + 94 TO 596 + 94	24.00	600.00	1600.00			1600.00		0.83	3.20	67.20	134.40				
STA. 596 + 94 TO 605 + 89	24-12	894.60	1862.43			1862.43		0.97	3.72	78.22	156.44				
STA. 605 + 89 TO 607 + 38	12.00	149.40	199.20	73.33	37.00	125.87		0.10	0.40	8.37	16.73				
MEDIAN CROSS OVERS															
STA. 294 + 30 TO 295 + 10	2.70	80.00	24.00			24.00		0.01	0.05	1.01	2.02				
STA. 302 + 16 TO 303 + 16	2.70	100.00	30.00			30.00		0.02	0.06	1.26	2.52				
STA. 306 + 95 TO 307 + 46	2.70	51.00	15.30			15.30		0.01	0.03	0.64	1.29				
STA. 309 + 85 TO 310 + 33	2.70	48.00	14.40			14.40		0.01	0.03	0.60	1.21				
STA. 314 + 00 TO 315 + 15	7.50	115.00	120.20			120.20		0.06	0.24	5.05	10.10				
STA. 318 + 29 TO 318 + 98	14.00	69.00	107.33			107.33		0.06	0.21	4.51	9.02				
STA. 329 + 60 TO 330 + 18	21.00	58.00	135.33			135.33		0.07	0.27	5.68	11.37				
STA. 335 + 23 TO 336 + 23	21.00	100.00	233.33			233.33		0.12	0.47	9.80	19.60				
STA. 340 + 23 TO 340 + 81	11.00	58.00	70.89			70.89		0.04	0.14	2.98	5.95				
STA. 351 + 85 TO 352 + 59	21.00	74.00	172.67			172.67		0.09	0.35	7.25	14.50				
STA. 381 + 37 TO 382 + 50	21.00	113.00	263.67			263.67		0.14	0.53	11.07	22.15				
STA. 399 + 46 TO 400 + 54	21.50	108.00	258.00			258.00		0.13	0.52	10.84	21.67				
STA. 460 + 94 TO 461 + 99	50.90	105.00	593.83			593.83		0.31	1.19	24.94	49.88				
STA. 491 + 40 TO 491 + 96	0.00	56.00	421.20				421.20	0.22	0.84	17.69	35.38				
STA. 565 + 13 TO 566 + 00	30.00	87.00	290.00			290.00		0.15	0.58	12.18	24.36				
STA. 585 + 56 TO 586 + 49	17.00	93.00	175.67			175.67		0.09	0.35	7.38	14.76				
STA. 589 + 82 TO 590 + 71	30.00	89.00	296.67			296.67		0.15	0.59	12.46	24.92				
STA. 602 + 00 TO 605 + 85	0.00	385.00	438.50			438.50		0.23	0.88	18.42	36.83				
SUB-TOTAL				347	174	23,268	14,252	19.7	75.7	1,590	3,181				

SCHEDULE OF QUANTITIES

PLOT DATE = 06-07-06
FILE NAME = KM-main CADD file.dgn