

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44,45)RS-5, (46-1)RS-7, 45-(RB, RB-2, BR)	PEORIA	82	23
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH FT	LENGTH FT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REM. BUTT JOINT SQ YD	TEMPORARY RAMP SQ YD	HOT-MIX ASPHALT SURFACE REM. 2.25 IN SQ YD	HOT-MIX ASPHALT SURFACE REM. 0.5 IN SQ YD	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT TON	AGGREGATE MATERIALS PRIME COAT TON	POLYMERIZED LEVEL BINDER (MACHINE METHOD), N50 TON	POLYMERIZED HMA SURFACE CSE MIX "D", N70 TON	HOT-MIX ASPHALT SHOULDERS				
												LEFT AREA SQ YD	LEFT SIDE TON	RIGHT AREA SQ YD	RIGHT SIDE TON	
WESTBOUND SIDEROADS																
MCKEE STREET																
STA. 302 + 43			138.40	138.40	16.70			0.07	0.28	5.81	11.63					
Private Entrance Sta. 307 + 21			100.00	100.00	16.70			0.05	0.20	4.20	8.40					
CAMERON LANE																
STA. 335 + 70			687.66	126.67	18.30	560.99		0.36	1.38	28.88	57.76					
POWELL LANE																
STA. 381 + 93			338.10	80.00	20.00	258.10		0.18	0.68	14.20	28.40					
WEST FIRST STREET																
STA. 400 + 03			345.00	87.00	22.00	258.00		0.18	0.69	14.49	28.98					
WALNUT STREET																
STA. 461 + 47			1008.00	340.00	71.10	668.00		0.52	2.02	42.34	84.67					
REED CITY ROAD																
STA. 491 + 77			171.60	171.60	27.00			0.09	0.34	7.21	14.42					
JACKSON STREET																
STA. 565 + 56			86.00	86.00	23.00			0.04	0.17	3.61	7.23					
KINGSTON MINES ROAD																
STA. 590 + 12			139.90	139.90	35.00			0.07	0.28	5.88	11.75					
SUB-TOTAL																
				1,270	250	1,745		1.6	6.0	127	253					

SCHEDULE OF QUANTITIES