

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(44,45)RS-5, (46-1)RS-7, (45-1)RB, RB-2, BR1	PEORIA	82	24
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

**TABULATION OF RESURFACING QUANTITIES**

LOCATION	TOTAL ROADWAY WIDTH FT	LENGTH FT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REM. BUTT JOINT SQ YD	TEMPORARY RAMP SQ YD	HOT-MIX ASPHALT SURFACE REM. 2.25 IN SQ YD	HOT-MIX ASPHALT SURFACE REM. 0.5 IN SQ YD	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT TON	AGGREGATE MATERIALS PRIME COAT TON	POLYMERIZED LEVEL BINDER SUPER, IL-4.75 METHOD), N50 TON	POLYMERIZED HMA SURFACE CSE MIX "D", N70 TON	HOT-MIX ASPHALT SHOULDERS				
												LEFT AREA SQ YD	LEFT SIDE TON	RIGHT AREA SQ YD	RIGHT SIDE TON	
<b>EASTBOUND SIDEROADS</b>																
<b>CAMERON LANE</b>																
STA.	335 + 70		283.80	123.83	17.00	159.97		0.15	0.57	11.92	23.84					
<b>WHEELER ROAD</b>																
STA.	340 + 53		139.80	139.80	15.60			0.07	0.28	5.87	11.74					
<b>POWELL LANE</b>																
STA.	381 + 93		193.00	193.00	25.00			0.10	0.39	8.11	16.21					
<b>WEST FIRST STREET</b>																
STA.	400 + 03		345.60	83.33	17.00	262.27		0.18	0.69	14.52	29.03					
<b>CATERPILLAR / LONZA ENTER</b>																
STA.	461 + 47		2701.10	121.00	65.00	1059.10		1.40	5.40	113.45	226.89					
<b>TERMINAL ROAD</b>																
STA.	519 + 83		1039.80	147.00	37.00	892.80		0.54	2.08	43.67	87.34					
<b>JACKSON ROAD</b>																
STA.	565 + 56		307.40	141.67	27.00	165.73		0.16	0.61	12.91	25.82					
<b>WASHINGTON ROAD</b>																
STA.	586 + 01		298.40	87.00	22.00	211.40		0.16	0.60	12.53	25.07					
<b>PEARL ROAD</b>																
STA.	590 + 12		439.90	106.67	26.70	333.23		0.23	0.88	18.48	36.95					
<b>SUB-TOTAL</b>				1,143	252	3,085		3	11.5	241.5	483					
<b>SUB-TOTAL (FROM SHEET 21)</b>				1,270	250	1,745		1.6	6.0	127	253					
<b>SUB-TOTAL (FROM SHEET 20)</b>						23,551	550	11.5	57.5	898	1,795	930				
<b>SUB-TOTAL (FROM SHEET 19)</b>						20,402		9.9	48.3			2,957				
<b>SUB-TOTAL (FROM SHEET 18)</b>						8,243		6.0	29.8						1,767	
<b>SUB-TOTAL (FROM SHEET 17)</b>						45,562		21.1	105.7						6,415	
<b>SUB-TOTAL (FROM SHEET 16)</b>				347	174	23,268	14,252	19.7	75.7	1,590	3,181					
<b>SUB-TOTAL (FROM SHEET 15)</b>				1,640	819	109,201	17,188	66.6	256.1	5,377	10,754					
<b>GRAND-TOTAL</b>				4,400	1,495	235,057	31,990	139.4	590.6	8,233.5	16,466				12,069	

SURFACE TYPE	BIT PR COAT	AGG PR COAT
	*(GAL/SQ YD)	(LBSQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW BITUMINOUS COURSES	0.03	2

\*0.004 TONS/GAL

SURFACE TYPE	
BIT. SURF. COURSES	112 LB /SQ YD/IN
ALL OTHER BIT.	112 LB /SQ YD/IN
AGGREGATE SHOULDERS	2.05 TONS/CUYD

SCHEDULE OF QUANTITIES