

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	Fulton	37	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* D4 CULVERT EXT/ REPAIR 2007

# SCHEDULE OF QUANTITIES

CODE NO.28000400

PERIMETER EROSION BARRIER	
LOCATION	UNIT FOOT
Lt. Sta. 591+72.71 to Sta. 592+26.83	80
Lt. Sta. 591+89.23 to Sta. 592+05.38	17
<b>TOTAL = 97</b>	

CODE NO.28100107

STONE RIPRAP, CLASS A4	
LOCATION	UNIT SQ YD
Rt. Sta. 589+26 to Sta. 591+13	284.4
Rt. Sta. 591+13 to Sta. 591+23	25.6
Rt. Sta. 591+23 to Sta. 592+57	219.6
Lt. Sta. 589+99 to Sta. 591+92	315.3
Lt. Sta. 591+92 to Sta. 592+02	17.1
Lt. Sta. 592+02 to Sta. 592+78	208.2
<b>TOTAL = 1,071</b>	

CODE NO.28200200

FILTER FABRIC	
LOCATION	UNIT SQ YD
Rt. Sta. 589+26 to Sta. 591+13	284.4
Rt. Sta. 591+13 to Sta. 591+23	25.6
Rt. Sta. 591+23 to Sta. 592+57	219.6
Lt. Sta. 589+99 to Sta. 591+92	315.3
Lt. Sta. 591+92 to Sta. 592+02	17.1
Lt. Sta. 592+02 to Sta. 592+78	208.2
<b>TOTAL = 1,071</b>	

CODE NO.50901760

PIPE HANDRAIL	
LOCATION	UNIT FOOT
Rt STA. 591+17.6	16
<b>TOTAL = 16</b>	

CODE NO.28000500

INLET AND PIPE PROTECTION	
LOCATION	UNIT EACH
Rt. Sta. 591+17.91, 105.14'	1
Lt. Sta. 591+91.39, 77.12'	1
<b>TOTAL = 2</b>	

CODE NO.28100125

STONE RIPRAP, CLASS B3	
LOCATION	UNIT SQ YD
Lt. Sta. 591+88 to Sta. 592+46	58
<b>TOTAL = 58</b>	

CODE NO.28102630

STONE RIPRAP DITCH CHECKS	
LOCATION	UNIT EACH
Rt. Sta. 590+00 to Sta. 592+00	5
Lt. Sta. 591+00 to Sta. 592+69	8
<b>TOTAL = 13</b>	

CODE NO.54002020

EXPANSION BOLTS 3/4 INCH	
LOCATION	UNIT EACH
Lt STA. 591+23.53	8
<b>TOTAL = 8</b>	

CODE NO.48101200

AGGREGATE SHOULDERS, TYPE B, (WEDGE)	
LOCATION	UNIT TON
Lt. Sta. 589+77.50 to Sta. 592+92.74	9
Rt. Sta. 588+90.81 to Sta. 593+08.84	11
<b>TOTAL = 20</b>	

CODE NO.54390200

INSERTION CULVERT LINER 28"	
LOCATION	UNIT FOOT
STA. 591+55.66	159
<b>TOTAL = 159</b>	

CODE NO.50800105

REINFORCEMENT BARS	
LOCATION	UNIT POUND
Rt. Sta. 591+23.5	21.5
Rt. Sta. 591+17.6	195.2
<b>TOTAL = 216.7</b>	

CODE NO.	50102400	54202965	54213675	54248510	60222250
	CONCRETE REMOVAL	PIPE CULVERTS TYPE 4 RCCP 30"	PRECAST REINF. CONC. FLARED END SECTION 30"	CONCRETE COLLAR	MANHOLES TYPE A, 5'-DIAMETER, TYPE 37 GRATE
	CU YD	FOOT	EACH	CU YD	EACH
LOCATION					
Rt. Sta. 591+23.5		46.7		1.0	
Lt. Sta. 591+91.50	2.7	35.3	1		1
<b>TOTAL =</b>	<b>2.7</b>	<b>82</b>	<b>1</b>	<b>1.0</b>	<b>1</b>

CODE NO.63000000

STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	UNIT FOOT
Lt. Sta. 590+62.5 to Sta. 592+95	237.5
Rt. Sta. 589+75 to Sta. 592+37.5	262.5
<b>TOTAL = 500.00</b>	