

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(102-2,3)RS	WOODFORD	15	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FAP 412 ROUTE 1-39/US51				

LOCATIONS			BITUMINOUS SCHEDULE												
			BIT. MATERIAL PRIME COAT	AGR. MATERIAL PRIME COAT	POLYMERIZED HMA SURF CSE MAINLINE = 24' 1 1/2"	POLYMERIZED H M A BIND CSE MAINLINE = 24' 2 1/4"	HMA SURF CSE MIX D N 50 RAMP = 16' 1 1/2"	H M A BIND CSE IL - 19.0 N50			H M A SURF CSE MIX C N50		AGG SHLDR LT & RT	MATERIAL TRANSFER DEVICE	SHOULDER RUMBLE STRIP
STATION	TO	STATION	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	FEET
MAINLINE															
N.B.															
710+00	TO	850+90	12.02	112.7	3,269	4,903								8,172	
52+80	TO	130+90	6.66	62.5	1,812	2,718								4,530	
Shoulders															
710+00	TO	850+90	8.02	75.1					3,269		2,179		2,008		28,180
52+80	TO	130+90	4.44	41.7					1,812		1,208		1,113		15,620
MAINLINE															
S.B.															
710+00	TO	850+90	12.02	112.7	3,269	4,903								8,172	
52+80	TO	148+00	8.12	76.2	2,209	3,313								5,522	
Shoulders															
710+00	TO	850+90	8.02	75.1					3,269		2,179		2,008		28,180
52+80	TO	148+00	5.42	50.8					2,209		1,472		1,357		19,040
RAMPS															
RAMP "A"			0.40	3.8			109	164							
RAMP "B"			0.54	5.0			146	220							
RAMP "C"			0.40	3.8			109	164							
RAMP "D"			0.54	5.0			146	220							
Ramps Shoulders															
RAMP "A"			0.32	3.0						132		88	56		
RAMP "B"			0.42	4.0						173		115	80		
RAMP "C"			0.34	3.2						138		92	56		
RAMP "D"			0.36	3.4						148		98	80		
SUBTOTALS								767	10,558	590	7,039	394			
TOTALS			68.1	638	10,558	15,837	511		11,916		7,432		6,756	26,396	91,020

CLASS A PATCHING SCHEDULE 10"											
LOCATION	PATCH UNITS	CL A PATCH						SAW CUTS FOOT	TIE BARS EACH	PATCH REIF SQ.YD	
		TYPE II		TYPE III		TYPE IV					
		NO.	SQ.YD	NO.	SQ.YD	NO.	SQ.YD				
S.B.D.L.											
STA 165+90 TO STA 56+90	1	4	31	1	16	6	383	1,491	252	430	
STA 842+36 TO STA 789+56	2	2	15	3	55	7	333	1,485	208	403	
STA 789+56 TO STA 736+76	3	11	90	4	67	4	165	1,635	100	322	
STA 736+76 TO STA 712+50	4	18	144	3	53	5	161	2,121	121	358	
N.B.D.L.											
STA 727+88 TO STA 849+98	5	7	47	1	17	0	0	504	0	64	
STA 53+27 TO STA 125+77	6	4	32	0	0	3	161	761	103	193	
N.B.P.L.											
STA 96+99 TO STA 122+13	7	2	13	0	0	1	29	272	38	42	
+10% BREAK-UP				37		21		123	82	181	
TOTAL				409		229		1,355	9,096	904	1,993

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____ HORIZ. _____

DRAWN BY _____
CHECKED BY _____