

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	(102-2,3)RS	WOODFORD	15	8
STA.	TO STA.			
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* FAP 412 ROUTE 1-39/US51				

LOCATION	TEMPORARY PAVEMENT MARKING LINE					
	EPOXY PAVEMENT MARKING LINE					PREF PLASTIC PAVT MARKING TYPE B LINE - 6" CENTER LINE SKIP DASH (WHITE) FT
	4"		8"	12"		
	LT EDGE OF PVT 4" SOLID (YELLOW) FT	RT EDGE OF PVT 4" SOLID (WHITE) FT	@ ENTR RAMP ONLY 4" SKIP DASH (WHITE) FT	@ THE RAMPS 8" SOLID (WHITE) FT	@ THE RAMPS CHEVRON 12" SOLID (WHITE) FT	
	I - 39					
N.B.						
710+00 TO 850+90	14090	13380				3523
52+80 TO 130+90	7810	6585				1953
S.B.						
710+00 TO 850+90	14090	13380				3523
52+80 TO 148+00	9520	8295				2380
RAMP A & RAMP C		1660	200	1640	874	
RAMP B & RAMP D		2690		1500		
SUB - TOTALS	45,510	45,990	200			
TOTALS		91,700		3,140	874	11,378

LOCATION	RAISED REF PAVEMENT MARKERS REMOVAL EACH		RAISED REF PAVEMENT MARKERS EACH	
	N.B.			
	710+00 TO 850+90	352		352
52+80.0 TO 130+90	195		195	
S.B.				
710+00 TO 850+90	352		352	
52+80.0 TO 148+00	238		238	
RAMPS				
A	79		79	
C	79		79	
TOTAL	1,296		1,296	

PAVEMENT MARKING SCHEDULE				
LOCATION	SHORT TERM PAVEMENT MARKING		WORK ZONE PAVEMENT MARKING REMOVAL	
	FT		SQ FT	
	N.B.			
710+00 TO 850+90	2,818		939	
52+80 TO 130+90	1,562		521	
SHOULDERS				
710+00 TO 850+90	2,254		751	
52+80 TO 130+90	1,250		417	
S.B.				
710+00 TO 850+90	2,818		939	
52+80.0 TO 148+00	1,904		635	
SHOULDERS				
710+00 TO 850+90	2,254		751	
52+80.0 TO 148+00	1,523		508	
RAMPS				
A	299		100	
B	484		161	
C	299		100	
D	484		161	
TOTAL	17,950		5,983	

CONSTRUCTING TEST STRIP SURFACE COURSE	EACH
TOTAL	1

ENGINEER FIELD OFFICE TYPE A JOBSITE	CAL MO
TOTAL	4

MOBILIZATION JOBSITE	L SUM
TOTAL	1

TRAF CONT & PROT STD 701411 JOBSITE	EACH
TOTAL	8

TRAF CONT & PROT STD 701401 JOBSITE	L. SUM
TOTAL	1

TRAF CONTROL SURVEILLANCE JOBSITE	CAL DAY
TOTAL	64

LOCATION	BUTT - JOINTS			TEMPORARY RAMPS		
	LENGTH	WIDTH	AREA	LENGTH	WIDTH	AREA
	FT	FT	SQ YD	FT	FT	SQ YD
N.B.						
710+00 TO 850+90	60.0	40.0	266.7	40.0	10.0	44.4
52+80.0 TO 130+90	60.0	40.0	266.7	40.0	10.0	44.4
S.B.						
710+00 TO 850+90	60.0	40.0	266.7	40.0	10.0	44.4
52+80.0 TO 148+00	60.0	40.0	266.7	40.0	10.0	44.4
RAMPS						
A	30.0	26.0	86.7	26.0	5.0	14.4
B	30.0	26.0	86.7	26.0	5.0	14.4
C	30.0	26.0	86.7	26.0	5.0	14.4
D	30.0	26.0	86.7	26.0	5.0	14.4
TOTAL			1,413			236

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. HORIZ.
 DATE
 DRAWN BY
 CHECKED BY