

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	MCLEAN	49	4

\* (57-21B&57-22B)&BDR

# SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI 74  
SECTION (57-21B & 57-22B) & BDR  
MCLEAN COUNTY

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	S.N. 057-0120	S.N. 057-0121	S.N. 057-0126	S.N. 057-0129
					100% STATE SFTY-2A	100% STATE SFTY-2A	100% STATE SFTY-2A	100% STATE SFTY-2A
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)		GALLON	258.0	67.0	67.0	80.0	44.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90		TON	311.0	94.0	94.0	79.0	44.0
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)		SQ YD	2,581.0	670.0	670.0	800.0	441.0
50102400	CONCRETE REMOVAL		CU YD	23.7	0.0	0.0	0.0	23.7
50300255	CONCRETE SUPERSTRUCTURE		CU YD	23.7	0.0	0.0	0.0	23.7
50300530	FLOOR DRAIN EXTENSION		EACH	24.0	0.0	0.0	0.0	24.0
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	3,390.0	0.0	0.0	0.0	3,390.0
50800515	BAR SPLICERS		EACH	24.0	0.0	0.0	0.0	24.0
67100100	MOBILIZATION		L SUM	1.0	0.25	0.25	0.25	0.25
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402		EACH	4.0	1.0	1.0	1.0	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406		L SUM	1.0	0.25	0.25	0.25	0.25
70400100	TEMPORARY CONCRETE BARRIER		FOOT	1,812.5	475.0	450.0	487.5	400.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER		FOOT	1,837.5	462.5	462.5	500.0	412.5
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"		FOOT	201.0	52.0	52.0	63.0	34.0
X0320887	POLYMER CONCRETE		CU FT	6.4	0.0	0.0	0.0	6.4
X0321468	PLUG EXISTING DECK DRAINS		EACH	70.0	12.0	12.0	36.0	10.0
X0322932	SILICONE JOINT SEALER, 1.5"		FOOT	86.0	0.0	0.0	0.0	86.0
X0323076	SILICONE JOINT SEALER, 1 3/4"		FOOT	80.0	0.0	0.0	80.0	0.0
X0323077	SILICONE JOINT SEALER, 2 3/4"		FOOT	160.0	80.0	80.0	0.0	0.0
X7015005	CHANGEABLE MESSAGE SIGN		CAL DA	28.0	28.0	0.0	0.0	0.0
* X7200201	WIDTH RESTRICTION SIGNING		L SUM	1.0	0.25	0.25	0.25	0.25
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)		SQ YD	64.0	10.0	16.0	27.0	11.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)		SQ YD	362.0	32.0	91.0	179.0	60.0
Z0016200	DECK SLAB REPAIR (PARTIAL)		SQ YD	340.0	87.0	87.0	100.0	66.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3		EACH	4.0	1.0	1.0	1.0	1.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3		EACH	4.0	1.0	1.0	1.0	1.0

\*SPECIALTY ITEM