

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
.	**	LOGAN	111	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

80% FED. / 20% STATE

- FAP ROUTE 320 AT FAU ROUTE 77066
- (103, 221), N, TS

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 LOCATION OF WORK: IL 10/121 (WOODLAWN ROAD) AT OLD U.S. 66 (LINCOLN PARKWAY)

CODE NO.	ITEM	UNIT	URBAN TOTAL	I000-1A	I000-1A
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	45	45	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1	1	
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	45	45	
28000300	TEMPORARY DITCH CHECKS	EACH	7	7	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,973.7		1,973.7
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	1,417.1		1,417.1
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	256.8		256.8
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.5	7.5	
40600300	AGGREGATE (PRIME COAT)	TON	38	38	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,974.4		1,974.4
40600990	TEMPORARY RAMP	SQ YD	228.6		228.6



PLT DATE : 5/29/2007
 FILE NAME : \\saw\apps\6653284\10\summary.dgn
 PLOT SCALE : 100.0000 / IN.
 USER NAME : laughton

REVISIONS	
NAME	DATE
TMJ	03-07

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP ROUTE 320 (IL 10/121) AT
 FAU ROUTE 77066 (OLD US 66)
 LOGAN COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE 03-21-06
 DRAWN BY TMJ
 CHECKED BY VTY

Rev. 6-5-07