

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LOGAN	111	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- FAP ROUTE 320 AT FAU ROUTE 77066
- (103, 22)I, N, TS

80% FED. / 20% STATE

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES		URBAN			
LOCATION OF WORK: IL 10/121 (WOODLAWN ROAD) AT OLD U.S. 66 (LINCOLN PARKWAY)					
CODE NO.	ITEM	UNIT	TOTAL	I000-1A	I000-1A
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	177	177	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	36	36	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	574	574	
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2	2	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4	4	
60235900	INLETS, TYPE A, TYPE 5 FRAME, OPEN LID	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	4	4	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60500060	REMOVING INLETS	EACH	9	9	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,298	1,298	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	336	336	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	737	737	
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ FT	3,027	3,027	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	



PLOT DATE = 3/20/2007
 FILE NAME = c:\nrs\pcts\1052301\1052301summary.dgn
 PLOT SCALE = 100.0001 / IN.
 USER NAME = feaugh1

REVISIONS	
NAME	DATE
TMJ	03-07

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP ROUTE 320 (IL 10/121) AT
 FAU ROUTE 77066 (OLD US 66)
 LOGAN COUNTY

SCALE: VERT. DRAWN BY TMJ
 HORIZ. CHECKED BY VTY
 DATE 03-21-06

Rev. 6-5-07