

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LOGAN	111	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

FAP ROUTE 320 AT FAU ROUTE 77066
03, 22II, N, TS

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
LOCATION OF WORK: IL 10/121 (WOODLAWN ROAD) AT OLD U.S. 66 (LINCOLN PARKWAY)

F
80% Fed. 20% State
F
80% Fed. 20% State
HS
90% Fed. 10% STATE
⚠

CODE NO.	ITEM	UNIT	URBAN TOTAL	I000-1A	I000-1A	Y031-1F
* 84500120	REMOVE ELECTRIC SERVICE INSTALLATION	EACH	1			1
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	309			309
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	323			323
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,861			1,861
* 87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	840.5			840.5
* 87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO 18 6PAIR	FOOT	968.5			968.5
* 87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	2			2
* 87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	2			2
* 87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	48			48
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	13			13
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	2			2
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1			1
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	380			380
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1

* SPECIALTY ITEMS

PLOT DATE : 3/20/2007
FILE NAME : c:\prowork\7066\70663284\summary.dgn
PLOT SCALE : 1/8"=1'-0"
USER NAME : taugh11r1

REVISIONS	
NAME	DATE
TMJ	03-07

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP ROUTE 320 (IL 10/121) AT
FAU ROUTE 77066 (OLD US 66)
LOGAN COUNTY

SCALE: VERT.
HORIZ.
DATE 03-21-06

DRAWN BY TMJ
CHECKED BY VTY

⚠ Rev. 6-5-07

Rev.