

|                     |          |                  |              |           |
|---------------------|----------|------------------|--------------|-----------|
| F.A. RTE.           | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
| *                   | **       | LOGAN            | 111          | 9         |
| STA.                |          | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT |              |           |

80% FED. / 20% STATE

- \* FAP ROUTE 320 AT FAU ROUTE 77066
- \*\* (103, 22)I, N, TS

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
LOCATION OF WORK: IL 10/121 (WOODLAWN ROAD) AT OLD U.S. 66 (LINCOLN PARKWAY)

| CODE NO.  | ITEM                                                                                 | UNIT | URBAN TOTAL | I000-1A | I000-1A | Y031-1F |
|-----------|--------------------------------------------------------------------------------------|------|-------------|---------|---------|---------|
| *81021570 | CONDUIT, AUGURED 3" DIA., PVC                                                        | FOOT | 174         |         |         | 174     |
| *81021590 | CONDUIT, AUGURED 4" DIA., PVC                                                        | FOOT | 157         |         |         | 157     |
| *81400100 | HANDHOLE                                                                             | EACH | 3           |         |         | 3       |
| *81400300 | DOUBLE HANDHOLE                                                                      | EACH | 2           |         |         | 2       |
| *81900200 | TRENCH BACKFILL FOR ELECTRICAL WORK                                                  | FOOT | 4,373.5     |         |         | 4,373.5 |
| *81603025 | UNIT DUCT, 600 V, 2-1C NO. 4, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE | FOOT | 1,110       |         |         | 1,110   |
| *81603035 | UNIT DUCT, 600 V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE | FOOT | 3,898       |         |         | 3,898   |
| *82103900 | LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT                                       | EACH | 14          |         |         | 14      |
| *82104250 | LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOT-CELL CONTROL, 250 WATT                    | EACH | 4           |         |         | 4       |
| *82500605 | LIGHTING CONTOLLER PHOTOCELL RELAY                                                   | EACH | 1           |         |         | 1       |
| *83034400 | LIGHT POLE STEEL, 45' MH, TENON MOUNT                                                | EACH | 14          |         |         | 14      |
| *83600300 | LIGHT POLE FOUNDATION, 30" DIAMETER                                                  | FOOT | 92          |         |         | 92      |
| *83800650 | BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN                              | EACH | 14          |         |         | 14      |
| *84200500 | REMOVAL OF EXISTING LIGHTING UNIT-SALVAGE                                            | EACH | 9           |         |         | 9       |
| *84200805 | POLE FOUNDATION REMOVED, METAL                                                       | EACH | 9           |         |         | 9       |

\* SPECIALTY ITEMS

| REVISIONS |       |
|-----------|-------|
| NAME      | DATE  |
| TMJ       | 03-07 |
|           |       |
|           |       |
|           |       |
|           |       |
|           |       |
|           |       |
|           |       |
|           |       |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAP ROUTE 320 (IL 10/121) AT  
FAU ROUTE 77066 (OLD US 66)  
LOGAN COUNTY

SCALE: VERT.  
HORIZ.  
DATE 03-21-06

DRAWN BY TMJ  
CHECKED BY VTY