CONTRACT NO. 72900

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	•	LOGAN	111	41
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• 103 & 22(I,N,TS)

STA. 143+90.83 END
SEC. (103, 22) I,N,TS IMPROVEMENT
IL 10/121/WOODLAWN RD.

N

20 0 20 40
SCALE IN FEET

PLAN
SURVEYED BY
PLOTTED BY
ALIGNMENT CHECKED
GRADES CHECKED
STAKING NOTED BY
NOTE BOOK
NO.
DATE
BY
PLOT DATE = 3/20/2007
FILE NAME = c:\pw-p\dcts\d653384\sht+p&pdr-rng1101.dgn
PLOT SCALE = 20.0000 '/ IN.
USER NAME = tayg1rr1

BIT. LOT
VERIZON
CONC.
CONC. SW
EXIST. R.O.W.
12" CONC.
MAIN ST. O & C
MILLINGS CE
BIT. CE
IL 10 BIT.
MATCHLINE STA. 141+50.00
143
144
145+00
146
℄ FAP 320 (IL 10/121)
18" CONC.
AMEREN CILCO 4" GAS (STEEL)
GAS REG STA

+67.3, 48.9' RT
EXIST. INLET
RIM= 582.38
FL= 579.98(N)

+62.5, 37.0' RT
EXIST. INLET
RIM= 582.97
FL= 582.43
INV= 579.10(E)
INV= 579.76(S)
INV= 579.14(W)

+40.0, 33.7' RT
EXIST. INLET
RIM= 583.21
FL= 582.28
INV= 579.69(E)
INV= 579.66(W)

+48.7, 31.0' RT
EXIST. INLET
RIM= 583.45
FL= 580.19

LEGEND

CONSTRUCTION LIMITS ___ ___

PROFILE
SURVEYED BY
PLOTTED BY
GRADES CHECKED
STAKING NOTED BY
NOTE BOOK
NO.
DATE
BY
PLOT/LINE NOTATIONS CHKD

MATCHLINE STA. 141+50.00

	590	588	586	584	582	580	578	576	574
141+50	583.15	583.19	583.22	583.25	583.29	583.34	583.39	583.44	583.47
	583.17	**583.21**	**583.24**	**583.27**	**583.32**	**583.36**	**583.41**	**583.46**	**583.49**
142+00	583.50	583.54	583.57	583.64	583.73	583.88	584.02	584.15	584.28
	583.51								
142+50	584.36	584.45	584.57	584.70	584.83				
143+00									
143+50									
144+00									
144+50									
145+00									
145+50									
146+00									
146+50									
147+00									

FAP 320 (IL 10/121/WOODLAWN RD.) – RT. OF STA.