

* - FAI 55, FAI 72, FAI 155, FAI 172, FAP 302 (IL 336), FAP 310 (US 67), FAP 75 (IL 29), FAP 145 (IL 104)
 ** - D-6 SHOULDER RUMBLE STRIPS 2007
 *** - ADAMS, HANCOCK, LOGAN, MACOUPIN, MONTGOMERY, MORGAN, PIKE, SANGAMON & SCOTT

F.A. RYE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	15	5

STA. _____ TO STA. _____
 FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT

SHOULDER RUMBLE STRIP (CONT.)

LOCATION	NBDL LENGTH (FT)	NBPL LENGTH (FT)	SBDL LENGTH (FT)	SBPL LENGTH (FT)
I-155 LOGAN COUNTY				
Mile Markers 0.00 to 8.98 = 8.98mi. • 5,280ft. = 47,414ft.	47,414	47,414	47,414	47,414
Omissions				
Mi. Marker 0.31 NB SN 054-0050	-200	-200		
Mi. Marker 0.73 SB Exit Ramp to I-55 NB				-673
Mi. Marker 0.79 NB Entrance Ramp from I-55 SB			-1,160	
Mi. Marker 3.33 SB SN 054-0074			-590	-590
Mi. Marker 3.34 NB SN 054-0073	-590	-590		
Exit 6 NB Exit Ramp	-685			
Exit 6 NB Entrance Ramp	-1,259			
Exit 6 SB Exit Ramp		-675		
Exit 6 SB Entrance Ramp		-1,219		
Mi. Marker 7.08 SB SN 054-0080			-110	-110
Mi. Marker 7.09 NB SN 054-0081	-110	-110		
Mi. Marker 7.41 SB SN 054-0076			-190	-190
Mi. Marker 7.42 NB SN 054-0077	-190	-190		
Mi. Marker 8.21 to 8.98 SB			-4,066	-4,066
Total:	44,380	44,430	41,298	41,785
I-155 LOGAN COUNTY SUBTOTAL: 171,893				

LOCATION	EBDL LENGTH (FT)	EBPL LENGTH (FT)	WBDL LENGTH (FT)	WBPL LENGTH (FT)
I-72 SANGAMON COUNTY				
Mile Markers 79.55 to 95.78 & 103.52 to 124.66=37.37mi. =197,314ft.	197,314	197,314	197,314	197,314
Omissions				
Exit 82 EB Exit Ramp	-694			
Exit 82 EB Entrance Ramp	-1,160			
Exit 82 WB Exit Ramp			-653	
Exit 82 WB Entrance Ramp			-1,180	
Exit 91 EB Exit Ramp	-741			
Exit 91 EB Entrance Ramp	-1,125			
Exit 91 WB Exit Ramp			-683	
Exit 91 WB Entrance Ramp			-1,172	
Mi. Marker 92.19 WB SN 084-0148			-250	-250
Mi. Marker 92.21 EB SN 084-0149	-250	-250		
Mi. Marker 93.24 WB SN 084-0128			-220	-220
Mi. Marker 93.25 EB SN 084-0127	-220	-220		
Exit 93 EB Exit Ramp	-661			
Exit 93 EB Entrance Loop	-1,205			
Exit 93 EB Entrance Ramp	-1,176			
Exit 93 WB Exit Ramp			-705	
Exit 93 WB Entrance Ramp			-1,119	
Mi. Marker 103.69 I-55 NB to I-72 EB Entrance Ramp	-200			
Mi. Marker 103.71 I-72 WB to I-55 NB Exit Ramp			-366	
Exit 104 EB Exit Ramp	-790			
Exit 104 EB Entrance Ramp	-1,146			
Exit 104 WB Exit Ramp			-605	
Exit 104 WB Entrance Ramp			-1,017	
Mi. Marker 106.48 EB SN 084-0151	-955	-955		
Mi. Marker 107.10 WB SN 084-0152			-955	-955
Exit 108 EB Exit Ramp	-765			
Exit 108 EB Entrance Ramp	-1,302			
Exit 108 WB Exit Ramp		-646		
Exit 108 WB Entrance Ramp		-996		
Exit 114 EB Exit Ramp	-666			
Exit 114 EB Entrance Ramp	-1,089			
Exit 114 WB Exit Ramp		-665		
Exit 114 WB Entrance Ramp		-1,179		
Mi. Marker 116.69 WB SN 084-0157			-200	-200
Mi. Marker 116.70 EB SN 084-0158	-200	-200		

SHOULDER RUMBLE STRIP (CONT.)

LOCATION	EBDL LENGTH (FT)	EBPL LENGTH (FT)	WBDL LENGTH (FT)	WBPL LENGTH (FT)
I-72 SANGAMON COUNTY (CONT.)				
Exit 122 EB Exit Ramp	-692			
Exit 122 EB Entrance Ramp	-1,197			
Exit 122 WB Exit Ramp			-716	
Exit 122 WB Entrance Ramp			-1,160	
Mi. Marker 124.23 EB SN 084-0163	-170	-170		
Mi. Marker 124.24 WB SN 084-0164			-170	-170
Total:	180,910	192,033	186,143	195,519
I-72 SANGAMON COUNTY SUBTOTAL: 754,605				

LOCATION	EBDL LENGTH (FT)	EBPL LENGTH (FT)	WBDL LENGTH (FT)	WBPL LENGTH (FT)
I-72 MORGAN COUNTY				
Mile Markers 57.15 to 79.55 = 22.40mi. • 5,280ft. = 118,272ft.	118,272	118,272	118,272	118,272
Omissions				
Exit 60 EB Exit Ramp	-675			
Exit 60 EB Loops & SN 069-0056	-1,296			
Exit 60 EB Entrance Ramp	-1,253			
Exit 60 WB Exit Ramp			-635	
Exit 60 WB Loops & SN 069-0055			-1,186	
Exit 60 WB Entrance Ramp			-1,160	
Mi. Marker 61.28 EB SN 069-0056				
Mi. Marker 61.29 WB SN 069-0055				
Mi. Marker 62.79 EB SN 069-0058	-145	-145		
Mi. Marker 62.80 WB SN 069-0057			-145	-145
Exit 64 EB Exit Ramp	-702			
Exit 64 EB Entrance Ramp & SN 069-0035	-1,564			
Exit 64 WB Exit Ramp			-703	
Exit 64 WB Entrance Ramp			-1,188	
Mi. Marker 65.42 EB SN 069-0035		-165		
Mi. Marker 65.43 WB SN 069-0036			-165	-165
Mi. Marker 67.67 EB SN 069-0038	-175	-175		
Mi. Marker 67.68 WB SN 069-0039			-175	-175
Mi. Marker 68.22 EB SN 069-0040	-280	-280		
Mi. Marker 68.23 WB SN 069-0041			-280	-280
Mi. Marker 68.55 WB SN 069-0043			-265	-265
Mi. Marker 68.56 EB SN 069-0042	-265	-265		
Exit 68 EB Exit Ramp	-660			
Exit 68 EB Entrance Ramp	-1,170			
Exit 68 WB Exit Ramp			-660	
Exit 68 WB Entrance Ramp			-1,174	
Mi. Marker 70.49 EB SN 069-0048	-250	-250		
Mi. Marker 70.49 WB SN 069-0049			-250	-250
Exit 76 EB Exit Ramp	-647			
Exit 76 EB Entrance Ramp	-1,104			
Exit 76 WB Exit Ramp			-699	
Exit 76 WB Entrance Ramp			-1,171	
Mi. Marker 79.33 WB SN 069-0059			-147	-147
Mi. Marker 79.34 EB SN 069-0060	-147	-147		
Total:	107,939	116,845	108,269	116,845
I-72 MORGAN COUNTY SUBTOTAL: 449,898				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 VARIOUS ROUTES
 SECTION D-6 SHLDR RUMBLE STRIPS 2007
 VARIOUS COUNTIES
 SCALE: VERT. _____ HORIZ. _____
 DATE _____ DRAWN BY _____ CHECKED BY _____

PLOT DATE = 3/23/2007
 FILE NAME = shtsch.dgn
 USER NAME = vevanda