CONTRACT NO. 72B04

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	15	8
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* - FAI 55, FAI 72, FAI 155, FAI 172, FAP 302 (IL 336), FAP 310 (US 67), FAP 75 (IL 29), FAP 745 (IL 104)

** - D-6 SHOULDER RUMBLE STRIPS 2007

*** - ADAMS, HANCOCK, LOGAN, MACOUPIN, MONTGOMERY, MORGAN, PIKE, SANGAMON & SCOTT

SHOULDER RUMBLE STRIP (CONT.)

LOCATION IL 104 ADAMS COUNTY	EBDL LENGTH (FT)	EBPL LENGTH (FT)	WBDL LENGTH (FT)	WBPL LENGTH (FT)
Mile Markers 5.89 to 12.46 = 6.57mi. * 5,280ft. = 34,690ft.	34,690	34,690	34,690	34,690
Omissions				
MI. Marker 5.94 EB Starting Point	-265	-265		
MI. Marker 5.98 Cross-over		-315		-315
MI. Marker 6.30 Cross-over		-400		-400
MI. Marker 6.67 Side Rd Skateland DR	-100	-515	-100	-515
MI. Marker 6.90 SN 001-0024 & 0070	-210	-210	-210	-210
MI. Marker 6.98 Side Rd	-100	-1,700		-1,700
MI. Marker 7.64 Side Rd Lilly Pond Rd	-100	-410	-100	-410
MI. Marker 7.75 Side Rd County Ln	-100	-500	-100	-500
MI. Marker 8.30 Side Rd Burton Rd	-100	-390	-100	-390
MI. Marker 8.65 Side Rd Fowler Rd	-100	-560	-100	-560
MI. Marker 9.00 Cross-over	-75	-430	-75	-430
MI. Marker 9.40 Side Rd	-75	-620	-75	-620
MI. Marker 10.18 Side Rd Ellington Rd	-100	-690	-100	-690
MI. Marker 10.25 Cross-over	-100	-406		-406
MI. Marker 11.17 Side Rd 1600th St	-100	-640	-100	-640
MI. Marker 11.54 Side Rd Baldwin Airport Rd	-75	-610	-100	-610
MI. Marker 11.85 CrossOover	-75	-615	-75	-615
MI. Marker 12.20 Side Rd Paloma Rd	-100	-600	-100	-600
Total:	32,915	24,814	33,355	25,079

IL 104 ADAMS COUNTY SUBTOTAL: 116,163

LOCATION IL 29 SANGAMON COUNTY	EBDL LENGTH (FT)	EBPL LENGTH (FT)	WBDL LENGTH (FT)	WBPL LENGTH (FT)
Mile Markers 1.13 to 5.17 = 4.04mi. * 5,280ft. = 21,331ft.	21,331	21,331	21,331	21,331
Omissions				
MI. Marker 1.14 IL 29 EB to I-55 SB Ramp	-100			
MI. Marker 1.18 I-55 SB to IL 29 WB Ramp			-330	
MI. Marker 1.35 IL 29 Entrance and Exit Loops	-637		-662	
MI. Marker 1.57 IL 29 WB to I-55 NB Ramp			-335	
MI. Marker 1.68 I-55 NB to IL 29 EB Ramp	-1,047			
MI. Marker 1.75 Side Rd Tansey Ave.		-610	-120	-610
MI. Marker 2.02 SN 084-0039 & 0040	-385	-385	-385	-385
MI. Marker 2.41 Side Rd Tuxhorn Rd	-550	-537	-75	-537
MI. Marker 2.67 Side Rd Hilltop Rd	-760	-400	-735	-400
MI. Marker 2.80 Cross-over		-400		-75
MI. Marker 3.30 Cross-over	-200	-100		-430
MI. Marker 3.80 Cross-over		-75		-75
MI. Marker 3.88 SN 084-0042 & 0043	-436	-436	-436	-436
MI. Marker 3.95 Cross-over		-364		-75
MI. Marker 4.30 Cross-over		-75		-75
MI. Marker 4.92 Side Rd Taft Ln	-10	-630	-650	-100
MI. Marker 5.09 Side Rd Camelot Dr		-500	-630	-115
MI. Marker 5.11 End Passing Lanes		-320		-320
Total:	17,206	16,499	16,973	17,698

IL 29 SANGAMON COUNTY SUBTOTAL: 68,376

SHOULDER RUMBLE STRIP SUMMARY

SUMMARY OF LOCATIONS	LENGTH (FT)
I-55 MACOUPIN COUNTY SUBTOTAL:	229,825
I-55 MONTGOMERY COUNTY SUBTOTAL:	57,401
I-55 SANGAMON COUNTY SUBTOTAL:	243,146
I-55 LOGAN COUNTY SUBTOTAL:	298,754
I-55 TOTAL:	829,126
I-155 LOGAN COUNTY SUBTOTAL:	171,893
I-155 TOTAL:	171,893
I-72 SANGAMON COUNTY SUBTOTAL:	754,605
I-72 MORGAN COUNTY SUBTOTAL:	449,898
I-72 SCOTT COUNTY SUBTOTAL:	134,942
I-72 PIKE COUNTY SUBTOTAL:	202,616
I-72 TOTAL:	1,542,061
I-172 PIKE COUNTY SUBTOTAL:	13,910
I-172 ADAMS COUNTY SUBTOTAL:	376,247
I-172 TOTAL:	390,157
IL 336 ADAMS COUNTY SUBTOTAL:	287,572
IL 336 HANCOCK COUNTY SUBTOTAL:	217,394
IL 336 TOTAL:	504,966
US 67 MORGAN COUNTY SUBTOTAL:	241,912
US 67 TOTAL:	241,912
IL 104 ADAMS COUNTY SUBTOTAL:	116,163
IL 104 TOTAL:	116,163
IL 29 SANGAMON COUNTY SUBTOTAL:	68,376
IL 29 TOTAL:	68,376
JOB TOTAL:	3,864,654

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

VARIOUS ROUTES
SECTION D-6 SHLDR RUMBLE STRIPS 2007
VARIOUS COUNTIES

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

PLOT DATE = 3/22/2007
FILE NAME = c:\pw_work\d653107\shtsch.dgn
PLOT SCALE = 188.4947 ' / IN.
USER NAME = vernende