

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			1000
			TOTAL QTY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3
40600300	AGGREGATE (PRIME COAT)	TON	13
40600990	TEMPORARY RAMP	SQ YD	67
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	477
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACE	TON	13
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	543
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5429
48101200	AGGREGATE SHOULDERS, TYPE B	TON	51
48203100	HOT-MIX ASPHALT SHOULDERS	TON	61
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	363
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	151
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	7000
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	19
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	19
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	396

\*SPECIALTY ITEMS

QUANTITIES  
FAP 538 (IL 94) & 685 (IL 9)  
SEC 112RS-3; (115,116,117)RS-5  
HANCOCK COUNTY