



CONTRACT NO. 74037				
FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	(6BR-2)B-1	CLAY	61	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DRAINAGE SCHEDULE		
LOCATION	CONCRETE HEADWALL FOR PIPE DRAINS	PIPE UNDERDRAINS FOR STRUCTURES 4"
	EACH	FOOT
STRUCTURE NO. 013-0041 - NW CORNER	1	37.5
STRUCTURE NO. 013-0041 - SW CORNER	1	37.5
STRUCTURE NO. 013-0041 - NE CORNER	1	37.5
STRUCTURE NO. 013-0041 - SE CORNER	1	37.5
TOTALS	4	150

BRIDGE APPROACH PAVEMENT SCHEDULE		
LOCATION	BRIDGE APPROACH PAVEMENT (SPECIAL)	PROTECTIVE COAT
	SQ YD	SQ YD
STRUCTURE NO. 013-0041 - NORTH APPROACH	138	141
STRUCTURE NO. 013-0041 - SOUTH APPROACH	138	141
TOTALS	276	282

PAVEMENT MARKING REMOVAL SCHEDULE			
LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
		SQ FT	SQ FT
STA 1506+25 TO STA 1513+75	SHORT-TERM	124	
STA 1506+25 TO STA 1513+75	TEMPORARY	567	
STA 1508+60 TO STA 1512+00, RT	EXISTING EDGE LINE		114
STA 1508+55 TO STA 1511+65, RT	EXISTING EDGE LINE		104
STA 1508+25 TO STA 1511+65	EXISTING CENTERLINE		30
TOTALS		691	248

PAVEMENT MARKING SCHEDULE				
LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING (3 APPLICATIONS)	PAINT PAVEMENT MARKING - LINE	TEMPORARY PAVEMENT MARKING - LINE
		FOOT	4"	4"
STA 1506+25 TO STA 1513+75	SKIP-DASH YELLOW CENTERLINE	228	200	200
STA 1506+25 TO STA 1513+75	SOLID WHITE EDGE LINE	144	1500	1500
TOTALS		372	1700	1700

PAVEMENT MARKERS AND REMOVAL SCHEDULE			
LOCATION	RRPM	RRPM (BRIDGE)	RRPM REMOVAL
	EACH	EACH	EACH
AT EXISTING LOCATIONS	9	1	9
TOTALS	9	1	9

GUARDRAIL SCHEDULE								
LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	SPBGR TYPE A	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKER-DIRECT APPLIED	TEMP SPBGR, TYPE A	TEMP. TBT TYPE 1 SPECIAL (TANGENT)
	EACH	FOOT	EACH	EACH	EACH	EACH	FOOT	EACH
STRUCTURE NO. 013-0041 - NW CORNER	1	112.5	1	1				
STRUCTURE NO. 013-0041 - SW CORNER	1	37.5	1	2				
STRUCTURE NO. 013-0041 - NE CORNER	1	37.5	1	2				
STRUCTURE NO. 013-0041 - SE CORNER	1	112.5	1	1				
STRUCTURE NO. 013-0041 - BRIDGE					4			
STAGE I				2		2	50	2
TOTALS	4	300	4	8	4	2	50	2

AGGREGATE SHOULDERS, TYPE B SCHEDULE	
LOCATION	TON
NORTHWEST QUADRANT	22
NORTHEAST QUADRANT	28
SOUTHWEST QUADRANT	23
SOUTHEAST QUADRANT	16
TOTAL	89

**ESCA**  
CONSULTANTS, INC.

DESIGNED BY: ELH 02/07  
DRAWN BY: HAG 02/07  
CHECKED BY: ELH 03/07  
APPROVED BY: RDP 03/07

SCHEDULES OF QUANTITIES  
FAP ROUTE 328 (US 45)  
SECTION (6BR-2)B-1  
CLAY COUNTY