CONTRACT NO. 76A94

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9251	28-3RS-1	ST. CLAIR	21	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED./20% STATE 1000 URBAN		
20200100	EARTH EXCAVATION	CU YD	94	94		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	26	26		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3		
40600300	AGGREGATE (PRIME COAT)	TON	13	13		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	377	377		
40600990	TEMPORARY RAMP	SQ YD	36	36		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	158	158		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	835	835		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7146	7146		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1832	1832		
44200128	PAVEMENT PATCHING, TYPE I, 11 INCH	SQ YD	72	72		
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	49	49		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	117	117		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12.5	12.5		
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	50	50		
~~67000400~~	~~ENGINEER'S FIELD OFFICE, TYPE A~~	~~CAL MO~~	~~3~~	~~3~~		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1248	1248		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12570	12570		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	31	31		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	104	104		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12570	12570		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	31	31		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	51	51		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	3	3		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	43	43		
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	15	15		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	35	35		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN		

* SPECIALTY ITEMS

PLOT DATE = 3/13/2007
FILE NAME = c:\projects\sd06607\plan\pln06607a.dgn
PLOT SCALE = 49.9999 ' / IN.
REFERENCE = REF