

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9251	28-3RS-1	ST. CLAIR	21	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	HMA SURFACE REMOVAL 1 1/2" (SQ YD)	HMA SURFACE REMOVAL 2 1/4" (SQ YD)	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE MATERIALS PRIME COAT (TON)	HMA BINDER CSE IL-19.0, N70 4 1/2" (TON)	LEVELING BINDER (MM) N70 3/4" (TON)	HMA SURF CSE MIX "D", N70 1 1/2" (TON)	AGGREGATE WEDGE SHOULDER TYPE B (TON)
STA 206+68 TO 207+23	138		0.1	0.2		5.8	11.6	
STA 207+23 TO 212+25	1116		0.3	1.7	22.9	46.9	105.3	17.0
STA 212+25 TO 217+18	1096		0.3	1.6	25.4	46.0	103.5	18.9
STA 217+18 TO 225+40	1827		0.6	2.7	35.7	76.7	173.3	26.6
STA 225+40 TO 232+32	1538		0.5	2.3	8.3	64.6	141.9	6.1
STA 232+32 TO 238+77	1433		0.4	2.2	33.6	60.2	134.6	25.0
STA 1238+77 TO 1241+10		725	0.2	1.1	13.0	30.4	65.7	9.7
STA 1241+10 TO 1244+66		1108	0.3	1.7	17.9	46.5	99.0	13.3
STA 1244+66 TO GUTTER					0.9		0.3	0.7
TOTALS	7,146	1,832	3	13	158	377	835	117

NOTE: THE QUANTITIES FOR AGGREGATE WEDGE SHOULDER, TYPE B INCLUDE EXCESS TO INSURE SMOOTH TRANSITIONS AT AGGREGATE ENTRANCES AND OTHER LOCATIONS AS DIRECTED BY THE RESIDENT ENGINEER.

LOCATION	SIDE	LENGTH (FT)	WIDTH (FT)	TYPE I (SQ YDS)	TYPE II (SQ YDS)
STA. 216+38	LT	8	10		8.9
STA. 216+38	RT	8	10		8.9
STA. 217+44	LT	4	10	4.4	
STA. 217+44	RT	4	10	4.4	
STA. 222+72	LT	4	10	4.4	
STA. 222+72	RT	4	10	4.4	
STA. 225+36	RT	8	10		8.9
STA. 228+00	LT	4	10	4.4	
STA. 228+00	RT	4	10	4.4	
STA. 230+64	LT	4	10	4.4	
STA. 230+64	RT	4	10	4.4	
STA. 232+22	LT	4	10	4.4	
STA. 232+22	RT	4	10	4.4	
STA. 232+75	LT	4	10	4.4	
STA. 232+75	RT	4	10	4.4	
STA. 238+56	LT	4	10	4.4	
STA. 1240+67	LT	4	14		6.2
STA. 1241+20	LT	4	14		6.2
ANTICIPATED FAILURES				14	10
TOTALS				72	49

LOCATION	SKIP-DASH YELLOW 4" (FT)	SOLID YELLOW 4" (FT)		SOLID WHITE 4" (FT)	SOLID YELLOW 4" (FT)	DOUBLE YELLOW 4" (FT)	DIAGONAL YELLOW 12" (FT)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	
	CENTERLINE	NO PASSING ZONE		EDGELINES	MEDIAN	MEDIAN	MEDIAN	ONE-WAY	TWO-WAY
		LT	RT						
STA. 206+68 TO 207+09				82		164	2	2	
STA. 207+09 TO 212+26	129	517		886					6
STA. 212+26 TO 216+32	102			776					5
STA. 216+32 TO 226+41	252		1009	1877					13
STA. 226+41 TO 230+58		417	417	733					5
STA. 230+58 TO 234+68	103	410		734					5
STA. 234+68 TO 236+85		217	217	434					3
STA. 236+85 TO 238+77	48		192	384					2
STA. 1238+77 TO 1239+83	27		106	212					1
STA. 1239+83 TO 1241+10				254		508	29	7	
STA. 1241+10 TO 1244+66				712	620			1	
STA. 1244+66 TO GUTTER				32					
SUBTOTALS	660	1561	1941	7116	620	672	31	10	41
TOTALS				12570			31		51

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES FAU ROUTE 9251 (IL 13) SECTION 28-3RS-1 ST. CLAIR COUNTY SCALE: VERT. _____ HORIZ. _____ DATE _____

DRAWN BY _____
CHECKED BY _____