

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1B-I-4	MADISON	9	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	SFTY-2A 100% STATE	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
* 78001110	PAINT PAVEMENT MARKING LINE 4"	FOOT	8955	8955	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	40	40	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	1475	1475	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	

INDEX OF SHEETS

- COVER SHEET
- SUMMARY OF QUANTITIES, INDEX OF SHEETS, GENERAL NOTES, LIST OF STANDARDS
- BRIDGE PLAN, ELEVATION, AND CROSS-SECTIONS
- DECK PATCHING SKETCHES, SPANS 1-4
- DECK PATCHING SKETCHES, SPANS 5-7
- DECK PATCHING SKETCHES, SPANS 8-12
- WB DECK PATCHING SCHEDULES
- EB DECK PATCHING SCHEDULES
- EB DECK PATCHING SCHEDULES & PATCHING SUMMARY

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price for the work.

This project shall utilize stage construction with a minimum lane width of 13' on the bridge deck through out the duration of the contract. All lanes shall be kept open during peak hours. See special provisions.

The Contractor shall place temporary cold mix in any area with potholes, deck depressions, spalls, or loose concrete, as directed by the Engineer.

The Wood River Maintenance Yard will provide traffic control for the RE to lay out patch locations. Contact Steve Wheeler at 618-259-1440 to coordinate the traffic control.

Illinois state law requires a 48-hour notice be given to utilities before digging. field marking of facilities may be obtained by contacting J.U.L.I.E. or for non-members, the utility company directly. agencies known to have facilities within the project area are as follows:

- * Ameren IP
- * AT&T Corporation
- * Buckeye Partners L.P. - Wood River Pipeline
- * Centerpoint Energy
- * Charter Communications, Inc.
- * City of Edwardsville
- * Explorer Pipelines
- * City of Granite City
- * Illinois American Water Company
- * Madison County Special Service Area #1
- * Mitchell Public Water District
- * AT&T Illinois
- * Level 3 Communications

(Members of J.U.L.I.E. (800) 892-0123 are indicated by *. Non-J.U.L.I.E. members must be notified individually.)

STANDARDS

- T01400-02
- T01401-03
- T02001-06

* SPECIALTY ITEMS