

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QTY.	I000-2A	Y 031-1F
20200100	EARTH EXCAVATION	CUYD	35	35	
20800150	TRENCH BACKFILL	CUYD	40	40	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	710	710	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	7	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7	7	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7	7	
25200110	SODDING, SALT TOLERANT	SQYD	710	710	
25200200	SUPPLEMENTAL WATERING	UNIT	5	5	
35101800	AGGREGATE BASE COURSE, TYPE B, 6"	SQYD	120	120	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,682	1,682	
40600300	AGGREGATE (PRIME COAT)	TON	34	34	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	250	250	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,177	1,177	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	725	725	
42101300	PROTECTIVE COAT	SQYD	967	967	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"	SQYD	320	320	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQFT	1,690	1,690	
42400800	DETECTABLE WARNINGS	SQFT	240	240	
44000100	PAVEMENT REMOVAL	SQYD	24	24	
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQYD	8,531	8,531	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	360	360	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,945	1,945	
44000600	SIDEWALK REMOVAL	SQFT	2,455	2,455	
44201737	CLASS D PATCHES, TYPE I, 8"	SQYD	50	50	
44201741	CLASS D PATCHES, TYPE II, 8"	SQYD	67	67	
44201745	CLASS D PATCHES, TYPE III, 8"	SQYD	80	80	
60213800	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	6	6	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	19	19	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16	16	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5	
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	365	365	
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	1,580	1,580	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	150	150	
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	63	63	
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	922	922	
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	688	688	
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	282	282	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	63	63	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	922	922	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	688	688	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	282	282	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	27		27
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	3		3
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	2		2
* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	22		22
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	58		58
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	59		59
* 81400100	HANDHOLE	EACH	1		1
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	32		32
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	699		699
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	353		353
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	851		851
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4
* 87900200	DRILL EXISTING HANDHOLE	EACH	5		5
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	1		1
* 88600100	DETECTOR LOOP, TYPE I	FOOT	198		198
* 89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	2		2
* 89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1		1
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1		1
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,175		1,175
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	237		237
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1		1
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1		1
* X8950200	REBUILD EXISTING HANDHOLE	EACH	1		1
XX003036	STORM SEWERS, PVC, SDR 26, 10"	FOOT	117	117	
Z0019600	DUST CONTROL WATERING	UNIT	5	5	

* DENOTES SPECIALITY ITEMS

Drawing file: W:\Projects\2005351 - 46th St Resurf & Sewer\summary of quantities.dwg Nov 01, 2005 - 11:24am

	◆ Civil Engineers	9933 Roosevelt Road Westchester, Illinois 60154-2780 Phone: 708/865-0300 Fax: 708/865-1212
	◆ Municipal Consultants	
	◆ Established 1911	

46th STREET RESURFACING PROJECT VILLAGE OF FOREST VIEW, ILLINOIS

SUMMARY OF QUANTITIES

SCALE:	NONE	SHEET	4 <hr/> 24
DRAWN BY:	MK/DMM/LEV/TSG		
BOOK NO.:	SDR33		
DATE:	11-1-06		
REVISION:	E.H.E. NO.: 320-05-35101	OF	