

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: I000

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5154	04-00343-00-PV	WINNEBAGO	42	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

85414

	CODE NO.	ITEM	UNIT	QUANTITY
1	20200410*	EARTH EXCAVATION (SPECIAL)	CU YD	2,845
2	20200500*	EARTH EXCAVATION (WIDENING)	CU YD	2,978
3	20201200*	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200
4	25000350	SEEDING, CLASS 7	ACRE	1.22
5	25001000*	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.22
6	28000300	TEMPORARY DITCH CHECKS	EACH	4
7	28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	68
8	31101600*	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	3,333
9	35100300*	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	3,333
10	35101400	AGGREGATE BASE COURSE, TYPE B	TON	410
11	35501303	HOT-MIX ASPHALT BASE COURSE, 4 3/4"	SQ YD	3,333
12	35600712	HOT-MIX ASPHALT BASE COURSE WIDENING 9"	SQ YD	3,312
13	40200800*	AGGREGATE SURFACE COURSE, TYPE B	TON	50
14	40600200*	BITUMINOUS MATERIALS (PRIME COAT)	TON	36
15	40600300	AGGREGATE (PRIME COAT)	TON	56
16	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	8,944
17	40600982*	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	710
18	40603085	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70	TON	1,301
19	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,449
20	40800050*	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	814
21	44400100	FIBER GLASS FABRIC REPAIR SYSTEM	SQ YD	2,995
22	48100100	AGGREGATE SHOULDERS, TYPE A	TON	8,256
23	48203100	HOT-MIX ASPHALT SHOULDERS	TON	2,416
24	50100100*	REMOVAL OF EXISTING STRUCTURES	EACH	2
25	54205059*	PIPE CULVERTS, SPECIAL 24"	FOOT	98
26	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
27	54213879	STEEL END SECTIONS 24"	EACH	4
28	54247180*	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1
29	60242400*	INLETS, SPECIAL	EACH	1
30	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6.24
31	61140400*	STORM SEWERS, SPECIAL 15"	FOOT	64
32	Δ 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,218.75
33	Δ 63000025*	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	100.0
34	Δ 63100167*	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	10
35	67100100	MOBILIZATION	L SUM	1
36	70101700*	TRAFFIC CONTROL AND PROTECTION	L SUM	1
37	70103800*	TRAFFIC CONTROL (SPECIAL)	L SUM	1
38	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	22
39	70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,513
40	70300200	TEMPORARY PAVEMENT MARKING	FOOT	36,566
41	70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	12,693
42	Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	36,566
43	Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	126
44	Δ 78200455	BIDIRECTIONAL GUARD RAIL REFLECTORS	EACH	16
45	Δ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6
46	X0325295*	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 (SPECIAL)	FOOT	511
47	Z0005400*	BREAKER-RUN CRUSHED STONE	TON	410
48	Z0013798*	CONSTRUCTION LAYOUT	L SUM	1

* SPECIAL PROVISION PROVIDED Δ SPECIALTY ITEMS

BELTLINE ROAD - SUMMARY OF QUANTITIES