

GUARDRAIL SCHEDULE

LOCATION	SPBGR TY A (FT) 63000000	TR BAR TRM T1 SPL TAN (EACH) 63100167	TRAF BAR TERM T5A (EACH) 63100075	TERMINAL MARKER-DA (EACH) 78201000	EXISTING GUARDRAIL (TO REMAIN) (FT)
RT STA 75+55.00 TO 75+68.25			1		
RT STA 75+68.25 TO 76+87.00	118.75				
RT STA 76+87.00 TO 77+37.00		1		1	
RT STA 77+87.00 TO 78+37.00		1		1	
RT STA 78+37.00 TO 80+87.00	250.00				
RT STA 80+87.00 TO 81+37.00		1		1	
RT STA 81+37.00 TO 84+80.00					*343
RT STA 84+80.00 TO 146+80.00	6200.00				
RT STA 146+80.00 TO 147+30.00		1		1	
RT STA 147+70.00 TO 148+20.00		1		1	
RT STA 148+20.00 TO 154+20.00	600.00				
RT STA 154+20.00 TO 154+70.00		1		1	
LT STA 77+80.75 TO 78+30.75		1		1	
LT STA 78+30.75 TO 80+87.00	256.25				
LT STA 80+87.00 TO 81+37.00		1		1	
LT STA 81+77.00 TO 82+27.00		1		1	
LT STA 82+27.00 TO 84+52.00	225.00				
LT STA 84+52.00 TO 85+02.00		1		1	
TOTALS	7650	10	1	10	*343

*ESTIMATED QUANTITY (FOR INFORMATION ONLY - NOT A PAY ITEM)

PAINT PAVEMENT MARKINGS

LOCATION	TYPE	PT PVT MK LTRS & SYMB (ISO FT) 78001100	PAINT PVT MK LINE 4 (FOOT) 78001110		PAINT PVT MK LINE 24 (FOOT) 78001180
			WHITE	YELLOW	WHITE
STA 0+00.00 TO 186+46.00	30-10 SKIP DASH				
RT STA 81+00.00	LETTERS & SYMBOLS	61		3287	
LT STA 82+00.00	LETTERS & SYMBOLS	61			
LT STA 65+00.00 TO 90+00.00	NO PASSING			2500	30
RT STA 65+00.00 TO 90+00.00	NO PASSING			2500	30
LT STA 135+00.00 TO 165+00.00	NO PASSING			3000	
RT STA 135+00.00 TO 165+00.00	NO PASSING			3000	
LT STA 0+00.00 TO 1+20.00	EDGE LINE		185		
RT STA 0+00.00 TO 1+20.00	EDGE LINE		139		
LT STA 1+20.00 TO 185+87.21	EDGE LINE		18467		
RT STA 1+20.00 TO 185+87.21	EDGE LINE		18467		
LT STA 185+87.21 TO 186+46.00	EDGE LINE		78		
RT STA 185+87.21 TO 186+46.00	EDGE LINE		123		
SUBTOTALS			37459	14287	
TOTALS		122	51746		60

**LOCATIONS HAVE BEEN ESTIMATED. PLACE ACCORDING TO HIGHWAY STANDARD 780001-01.

SHORT-TERM PAVEMENT MARKINGS

LOCATION	TYPE	SHORT-TERM PAVT MKING (FOOT) 70300100	WORK ZONE PAVT MK REM (ISO FT) 70301000
		YELLOW	
AFTER BINDER COURSE PLACEMENT			
STA 0+00.00 TO 65+00.00	CENTERLINE	592	
STA 65+00.00 TO 90+00.00	NO PASSING ZONE	5000	
STA 90+00.00 TO 135+00.00	CENTERLINE	400	
STA 135+00.00 TO 165+00.00	NO PASSING ZONE	6000	
STA 165+00.00 TO 186+46.00	CENTERLINE	196	
AFTER SURFACE COURSE PLACEMENT			
STA 0+00.00 TO 65+00.00	CENTERLINE	592	197
STA 65+00.00 TO 90+00.00	NO PASSING ZONE	5000	1665
STA 90+00.00 TO 135+00.00	CENTERLINE	400	133
STA 135+00.00 TO 165+00.00	NO PASSING ZONE	6000	1999
STA 165+00.00 TO 186+46.00	CENTERLINE	196	65
TOTALS		24376	4059

CULVERT REMOVAL SCHEDULE

LOCATION	TYPE	SIZE	REM EXIST CULVERTS (FT) 50105210
STA 0+11.95	CMP	30"	46
TOTAL			46

TRAFFIC CONTROL

LOCATION	TRAF CONT COMPL (L SUM) 70103700	MOBILIZATION (L SUM) 67100100
STA 0+00.00 TO 186+46.00	1	1
TOTALS	1	1

EARTHWORK SCHEDULE

LOCATION	EXCAVATION (CUT) (CU YD) 20200100	EXCAVATION (CUT) (ADJUSTED FOR SHRINKAGE) (CU YD)	EMBANKMENT (FILL) (CU YD)	EARTHWORK BALANCE WASTE (+) OR FURNISHED EXCAVATION (-) (CU YD) 20400800
STA. 0+00 TO 186+46 (VANTINE RD.)	278	210	3568	-3358
STA. 98+71.52 TO 99+51.79 (U.S. 34)	54	41	22	19
TOTALS	332	251	3550	-3339

(NOTE: PER BDE MANUAL CH. 64-2.02(g), USE SHRINKAGE FACTOR = 25%)
 (NOTE: EMBANKMENT IS FOR INFORMATION ONLY & NOT A PAY ITEM)
 (NOTE: ALL EARTHWORK QUANTITIES HAVE BEEN ESTIMATED)

CROSSROAD PIPE CULVERT SCHEDULE

LOCATION	P CUL 1 RC-E EORS 30 (FT) 54207165	PRCF END S EL EORS 30 (EACH) 54214725	TRENCH BACKFILL (CU YD) 20800150
0+40.00	52	2	14.9
TOTALS	52	2	14.9

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.S. 418 (VANTINE ROAD)
NAME	DATE	
		SCHEDULE OF QUANTITIES
SCALE: N/A	DRAWN BY: CGF	CHECKED BY: JUM
DATE: 1-5-07		