

FUND CODE: J000-2A

F.A.U. RTE. 6352 6412	SECTION 02-00218-00-SP	COUNTY MCLEAN	TOTAL SHEETS 35	SHEET NO. 5
STA.		TO STA.		
ILLINOIS FED. AID PROJECT				

CONTRACT NO. 91363

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
Δ *	87502500 TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2
Δ *	87601200 PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE II	EACH	2
Δ *	87702940 STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1
Δ *	87702970 STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	3
Δ	87800100 CONCRETE FOUNDATION, TYPE A	FOOT	6
Δ	87800200 CONCRETE FOUNDATION, TYPE D	FOOT	4
Δ *	87800415 CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	52
Δ	87900200 DRILL EXISTING HANDHOLE	EACH	1
Δ *	88040060 SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4
Δ *	88040090 SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12
Δ *	88040150 SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2
Δ *	88040160 SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2
Δ *	88102810 PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	8
Δ	88200410 TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	20
Δ *	88800100 PEDESTRIAN PUSH-BUTTON	EACH	8
Δ	89000100 TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
Δ *	89502380 REMOVE EXISTING HANDHOLE	EACH	11
Δ *	89502385 REMOVE EXISTING CONCRETE FOUNDATION	EACH	9
*	X0321905 STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	26
Δ *	X0322281 WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1
Δ *	X0322341 PULL & REINSTALL FIBER OPTIC CABLE	L SUM	1
Δ *	X0962500 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1
*	X6020125 RESTRICTED DEPTH INLET TYPE B, TYPE 3 FRAME AND GRATE	EACH	2
Δ *	X8730027 ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 IC	FOOT	600
Δ *	XX006163 REMOVE ELECTRICAL CABLE FROM CONDUIT (SPECIAL)	L SUM	1
*	XX006192 RESTRICTED DEPTH INLETS TYPE B, TYPE 1 4" FRAME, OPEN LID	EACH	2
*	XX006193 RESTRICTED DEPTH INLET, TYPE B, SALVAGED FRAME AND GRATE	EACH	2
*	XX006661 UNINTERRUPTABLE POWER SUPPLY	EACH	1
*	XX146400 STORM SEWER REMOVAL	FOOT	52
*	Z0013798 CONSTRUCTION LAYOUT	L SUM	1

* SEE SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 3-07
 DRAWN BY : S.M.W.
 CHECKED BY : J.T.P.