

# CONTINUED GENERAL NOTES:

## F.A.U. 7695/ 14<sup>th</sup> STREET MIXTURE REQUIREMENTS

LOCATION	14 <sup>th</sup> STREET, 0+00 ~ 33+82
MIXTURE USE	SURFACE
AC/PG	PG 64-22
DESIGN AIR VOIDS	4.0 % @ Ndes = 50
MIX. COMPOSITION (GRADATION MIX)	IL 9-5
FRICITION AGGREGATE	MIX D

## F.A.U. 7680/S. 19<sup>th</sup> STREET

### PATCHING MIXTURE REQUIREMENTS

LOCATION	ALL PATCHING LOCATIONS
MIXTURE USE	PATCHING
AC/PG	PG 64-22
DESIGN AIR VOIDS	4.0% @ Ndes = 50
MIX COMPOSITIONS (GRADATION MIX)	IL 19.0
FRICITION AGGREGATE	N.A.

CITY OF MATTOON  
SECTION 06-00144-00-RS  
VARIOUS F.A.U. ROUTES  
JOB#: C-97-043-07  
PROJECT#: M5042(16)  
CONTRACT #: 95501  
COLES COUNTY  
SHEET 3 OF 35

# SUMMARY OF QUANTITIES

ITEM #	PAY ITEM	UNIT	QUANTITY
XX003140	SHORT - TERM PAVEMENT MARKING REMOVAL	FOOT	2,000.0
Z0048665	RAILROAD PROTECTION LIABILITY INSURANCE	LUMP SUM	1.0
40600100	BIFUMINOUS MATERIALS (PRIME COAT)	GALLON	2,847.0
40600300	AGGREGATE (PRIME COAT)	TON	14.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	791.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	897.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,060.0
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ. YD.	27.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ. YD.	32.3
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ. YD.	16.7
60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	34.0
66700105	PERMANENT SURVEY MARKERS (SPECIAL)	EACH	1.0
67100100	MOBILIZATION	LUMP SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LUMP SUM	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LUMP SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,000.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,890.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	705.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	357.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	244.8

\* SPECIALTY ITEMS