

SCHEDULE OF QUANTITIES

F.A.U. 7680/S. 19TH STREET

CITY OF MATTOON

SECTION 06-00144-00-RS

ROUTE: F.A.U. 7680

S. 19TH STREET

JOB#: C-97-043-07

PROJ#: M-5042(16)

CONTRACT#: 95501

COLES COUNTY

SHEET 16 OF 35

40600100 BITUMINOUS MATERIALS (PRIME COAT)

Lt. ~ Rt., 0+00 ~ 34+46 =856 GALLON
TOTAL =856 GALLON

44201765 CLASS D PATCH TYPE 2 10"

CL. ~ 10' Lt., 6+13 ~ 6+20 =7.8 SQ. YD.
 CL. ~ 10' Rt., 6+13 ~ 6+20 =7.8 SQ. YD.
 CL. ~ 12' Lt., 19+74 ~ 19+80 =8.0 SQ. YD.
 CL. ~ 13' Rt., 19+74 ~ 19+80 =8.7 SQ. YD.
TOTAL =32.2 SQ. YD.

7800200 THERMOPLASTIC PLASTIC PVT MK LINE 4"

DASHED 10' YELLOW 4"
 CL., 0+00 ~ 39+90 =1000.0 FOOT
SOLID WHITE 4"
 10' Lt. & Rt., 0+00 ~ 39+90 =7320.0 FOOT
TOTAL =8320.0 FOOT

40600300 AGGREGATE (PRIME COAT)

Lt. ~ Rt., 0+00 ~ 34+46 =4 TON
TOTAL =4 TON

44201769 CLASS D PATCH TYPE 3 10"

CL. ~ 12.5' Rt., 3+02 ~ 3+14 =16.7 SQ. YD.
TOTAL =16.7 SQ. YD.

78000650 THERMOPLASTIC PVT MK LINE 24"

SOLID WHITE 24" STOP BAR
 CL. ~ 30' Rt., 39+92 =30.0 FOOT
 ~ 30+78 =60.0 FOOT
TOTAL =90.0 FOOT

78000100 THPL PVT MK LTR & SYM

~30+78 = 122.4 SQ. FT.

40600982 HOT MIX ASPHALT SURFACE REMOVAL BUTT JOINT

12' Lt. ~ Rt., 0+00 ~ 0+25 =67.0 SQ. YD.
 12' Lt. ~ Rt., 30+60 ~ 30+75 =40.0 SQ. YD.
 12' Lt. ~ Rt., 30+81 ~ 30+96 =40.0 SQ. YD.
 12' Lt. ~ Rt., 34+21 ~ 34+46 =67.0 SQ. YD.
TOTAL =214.0 SQ. YD.

60300350 MANHOLE FRAMES TO ADJUST

6' Rt., 0+80 =1.0 EACH
 3' Lt., 3+03 =1.0 EACH
 8' Lt., 4+47 =1.0 EACH
 12' Lt., 4+90 =1.0 EACH
 11' Lt., 5+47 =1.0 EACH
 15' Lt., 5+87 =1.0 EACH
 12' Lt., 8+73 =1.0 EACH
 1' Rt., 19+82 =1.0 EACH
 10' Rt., 28+58 =1.0 EACH
TOTAL =9.0 EACH

40603335 HOT MIX ASPHALT SURFACE COURSE D 50

12' Lt. ~ Rt., 0+00 ~ 34+46 =650 TON
TOTAL =650 TON

44201761 CLASS D PATCH TYPE 1 10"

CL. ~ 10' Lt., 11+84 ~ 11+88 =4.5 SQ. YD.
 CL. ~ 10' Rt., 11+84 ~ 11+88 =4.5 SQ. YD.
 CL. ~ 10' Lt., 18+05 ~ 18+09 =4.5 SQ. YD.
 CL. ~ 10' Rt., 18+05 ~ 18+09 =4.5 SQ. YD.
 CL. ~ 10' Lt., 18+94.5 ~ 18+98.5 =4.5 SQ. YD.
 CL. ~ 10' Rt., 18+94.5 ~ 18+98.5 =4.5 SQ. YD.
TOTAL =27.0 SQ. YD.

66700105 PERMANENT SURVEY MARKER (SPECIAL)

4' Rt., 3+26 =1.0 EACH
TOTAL =1.0 EACH

40600625 LEVEL BINDER MM MIXC N50

12' Lt. ~ Rt., 0+25 ~ 6+00 =70 TON
 11' Lt. ~ Rt., 6+00 ~ 34+21 =335 TON
TOTAL =405 TON