

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9276	05-00029-02-RS	CAHOKIA	10	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 97311				

QUANTITY SCHEDULES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70			
STA	STA	Sq Yd	TON
SHEET #1			
00+12.00	to 05+00.00	1500	168.0
SHEET #2			
05+00.00	to 11+00.00	1733	194.1
SHEET #3			
11+00.00	to 17+00.00	1852	207.4
SHEET #4			
17+00.00	to 23+00.00	2240	250.8
SHEET #5			
23+00.00	to 29+00.00	1959	219.4
SHEET #6			
29+00.00	to 35+00.00	1959	219.4
SHEET #7			
35+00.00	to 38+70.50	1258	140.9
TOTAL			1400

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH			
Sta	Sta	Side	SQ FT
17+55.50	to 17+81.92	Rt	192
20+20.33	to 21+27.34	Rt	540
29+81.66	to 30+63.00	Lt	400
37+12.72	to 37+68.08	Lt	286
TOTAL			1418

THERMOPLASTIC PAVEMENT MARKING - LINE 4"		
Station	Station	FOOT
0+12.00	to 14+55.51	361
15+36.77	to 17+60.71	56
18+39.80	to 21+12.00	68
21+92.00	to 24+62.00	68
25+42.00	to 29+19.25	94
29+91.66	to 38+50.78	215
TOTAL		862

DETECTABLE WARNINGS		
Station	Side	SQ FT
17+71.00	Rt	6
21+27.34	Rt	6
29+81.66	Lt	6
Total		18

COMBINATION CURB AND GUTTER REMOVAL			
Station	Station	Side	FOOT
4+90.00	to 05+10.00	Lt	20
11+10.00	to 11+20.00	Lt	10
17+64.71	to 17+78.74	Rt	17
TOTAL			47

THERMOPLASTIC PAVEMENT MARKING - LINE 6"			
Station	Side	Side Road	FOOT
14+76.13	LT	Old Paris Ave	72
17+64.71			63
17+71.00	RT	Doris Ave	102
18+29.87			63
21+22.20	LT	Mullens Ave	102
21+22.20	RT	Mullens Ave	102
24+76.37	LT	Loretta Ave	96
24+74.37	RT	Loretta Ave	96
29+23.25			60
29+30.40	LT	Harvest Ave	90
29+29.25	RT	Harvest Ave	93
29+81.66			63
38+54.78			155
TOTAL			1157

SHORT-TERM PAVEMENT MARKING			
STA	STA	* of Applications	FOOT
00+12.00	to 38+70.50	3	1052

SIDEWALK REMOVAL			
Station	Station	Side	SQ FT
17+55.50	to 17+81.92	Rt	130
20+20.33	to 21+27.34	Rt	540
29+81.66	to 30+63.00	Lt	400
37+12.72	to 37+68.08	Lt	286
TOTAL			1356

THERMOPLASTIC PAVEMENT MARKING - LINE 12"			
Station	Side	Side Road	FOOT
14+82.00	LT	Old Paris Ave	15
17+60.71	RT		14
17+85.61	LT	Doris Ave	16
18+00.50	RT		19
18+39.80	LT		14
21+34.45	LT	Mullens Ave	18
21+52.00	RT	Mullens Ave	19
24+87.09	LT	Loretta Ave	17
25+02.00	RT	Loretta Ave	17
29+19.24	RT		14
29+40.53	LT	Harvest Ave	17
29+57.00	RT	Harvest Ave	17
29+91.66	LT		14
38+50.78	RT		25
TOTAL			236

WORK ZONE PAVEMENT MARKING REMOVAL				
STA	STA	* of Applications	Width (In)	SQ FT
00+12.00	to 38+70.50	3	4	351

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24			
Station	Station	Side	FOOT
4+90.00	to 05+10.00	Lt	20
11+10.00	to 11+20.00	Lt	10
17+64.71	to 17+78.74	Rt	17
TOTAL			47

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES

SCALE: VERT.
HORIZ.
DATE: 04/05/07

DRAWN BY: JJC
CHECKED BY: MAR