

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	02-1J-1J-2J-3MS-1	ALEXANDER	22	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	RURAL	
				100% STATE	
				ALEXANDER COUNTY	
				SOUTHBOUND LANES	NORTHBOUND LANES
				1000 QUANTITY	1000 QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	17,652.0	8,645.0	9,007.0
X0325750	PORTABLE CHANGEABLE MESSAGE SIGN	CAL MO	3.0	1.5	1.5
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE "D" NI05	TON	7,000.0	3,470.0	3,530.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, NI05	TON	10,652.0	5,175.0	5,477.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,376.0	3,670.0	3,706.0
40600300	AGGREGATE (PRIME COAT)	TON	126.5	61.2	65.3
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGWAYS	TON	12.0	6.0	6.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	1.0	1.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1,920.0	960.0	960.0
40600990	TEMPORARY RAMP	SQ YD	396.0	198.0	198.0
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	5,046.0	2,523.0	2,523.0
44200525	CLASS A PATCHES, TYPE 1, 8 INCH	SQ YD	140.0	47.0	93.0
44200529	CLASS A PATCHES, TYPE 2, 8 INCH	SQ YD	435.0	188.0	247.0
44200533	CLASS A PATCHES, TYPE 3, 8 INCH	SQ YD	98.0	0.0	98.0
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	265.0	81.0	184.0
44213000	PATCHING REINFORCEMENT	SQ YD	673.0	235.0	438.0
44213200	SAW CUTS	FOOT	4,096.0	1,438.0	2,658.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,350.0	722.0	628.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	11,118.0	5,530.0	5,588.0
64200105	SHOULDER RUMBLE STRIP	FOOT	58,761.0	29,390.0	29,371.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	1.5	1.5
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.0	0.5	0.5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	0.5	0.5
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.5	0.5
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	2,289.0	1,176.0	1,113.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	67,299.0	34,590.0	32,709.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	23,173.0	11,910.0	11,263.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	60,148.0	30,916.0	29,232.0
78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,151.0	3,674.0	3,477.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	470.0	248.0	222.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	470.0	248.0	222.0



PLOT DATE: 4/15/2007
 FILE NAME: C:\Users\jshuman\Documents\98905.dwg
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: jshuman

Rev. 5-30-07

* SPECIALTY ITEMS

Rev.