

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	18	8
STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		

*869 & 132
 **IRS-2(20XRS)(103,104,105)RS-2

MAINLINE RESURFACING SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	ROADWAY WIDTH (FT)	ROADWAY AREA (SQ YD)	HOT-MIX ASP. SURF. REM. 1 1/4"	HOT-MIX ASP. SURF. REM. 1 1/2"	HOT-MIX ASP. SURF. REM. 2 1/4"	TEMPORARY RAMP	HOT-MIX ASP. SUR. CSE. MIX D, N 90	LEVEL BINDER (MM) N90	BIT. MAT. PRIME COAT	AGG. PRIME COAT	AGG. SHOULDER TYPE B(1)			
				(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(GAL)	(TON)	(TON)			
GALATIA SECTION - STA. 1063+50 TO STA. 1570+00															
1063+50.00 TO 1108+79.30	4529.3	24.0	12078.1		12078.0		13.3	1046.3	506.6	2185.4	36.4	43.0			
EQ. STA. 1108+79.3 (BK.) = STA. 1113+00 (AH)															
1113+00.00 TO 1115+94.00	294.0	24.0	784.0		784.0		13.3	67.8	32.2	141.8	2.4	3.0			
1115+94.00 TO 1116+46.50															
BRIDGE OMISSION S. N. 083-0026 (GASSAWAY BRANCH)															
1116+46.50 TO 1119+10.00	263.5	24.0	702.7		703.0		13.3	60.8	28.8	127.1	2.2	3.0			
THRU GALATIA 1119+10.00 TO 1155+40.00	3630.0	24.0	9680.0		9680.0		0.0	837.5	406.6	1742.4	29.2	0.0			
1155+40.00 TO 1198+77.80	4337.8	24.0	11567.5		11568.0		13.3	1000.8	485.1	2093.0	34.8	41.0			
BRIDGE OMISSION S. N. 083-0027 (STREAM FROM HARRISBURG RESERVIOR)															
1198+77.80 TO 1199+32.30					3113		13.3	269.3	130.0	563.2	9.4	11.0			
1199+32.30 TO 1210+99.60	1167.3	24.0	3113		3113		13.3								
EQ. STA. 1210+99.6 (BK.) = STA. 1209+00 (AH)															
1209+00.00 TO 1369+95.00	16095.0	24.0	42920.0		42920.0		13.3	3713.4	1801.9	7765.8	129.4	153.0			
RAILROAD CROSSING (ILLINOIS CENTRAL)															
1369+95.00 TO 1370+35.00					8767.0		13.3	759.0	367.5	1586.2	26.4	31.0			
1370+35.00 TO 1403+22.60	3287.6	24.0	8766.9		8767.0		13.3								
EQ. STA. 1403+22.60 (BK.) = STA. 1400+96.80 (AH)															
1400+96.80 TO 1541+73.30	14076.5	24.0	37537.3		37538.0		13.3	3248.0	1575.9	4778.3	79.2	94.0			
1541+73.30 TO 1542+26.70					4976.0		26.6	430.4	208.8	900.2	15.0	18.0			
1542+26.70 TO 1560+92.40	1865.7	24.0	4975.2		4976.0		26.6								
BRIDGE OMISSION S. N. 083-0037 (MIDDLE FORK SALINE RIVER)															
1560+92.40 TO 1562+47.60					2007.0		26.6	173.6	83.6	363.0	6.0	7.0			
1562+47.60 TO 1570+00.00	752.4	24.0	2006.4		2007.0		26.6								
BRIDGE OMISSION S. N. 083-0038 (MIDDLE FORK DITCH)															
SUBTOTAL - GALATIA SECTION							0	124,454	9,680	159.6	11,607	5,627	22246	370.4	404
PANKEYVILLE SECTION - STA. 16+31 TO STA. 52+35															
16+31 TO 10+00	631.0	24.0	1683.9		1683.9		13.3	142.0	71.0	304.0	5.0	8.0			
EQ. STA. 10+00.00 (BK.) = STA. 0+00 (AH)															
+00 TO 7+14	714.1	24.0	1904.1		1904.1			160.0	80.0	343.0	6.0	9			
SN 083-0017 7+14 TO 7+76	61.9	24.0	165.0	165.0				12.0	15.0	15.0	1.0				
7+76 TO 18+00	1024.0	24.0	2731.0		2731.0			230.0	115.0	492.0	8.0	13			
18+00 TO 52+35	3435.0	24.0	9160.0		9160.0		13.3	769.0	385.0	1648.0	28.0				
SUBTOTAL - PANKEYVILLE SECTION							165	6,319	9160.0	26.6	1313	651.0	2802.0	48.0	30
PROJECT TOTALS							165	130,773	18,840	186.2	12,920	6,278	25,048	418.4	434

PLOT DATE = 2/10/2007
 FILE NAME = s:\projects\98945\98945.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mcorbett