



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2007

SUBJECT: FAI Route 57 / 64 (I-57 / 64)
Project HPD-F-0520 (001)
Section (41-3) HBK
Jefferson County
Contract No. 98963
Item No. 292, June 15, 2007 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 – 16 of the Schedule of Prices.
2. Revised sheets 4, 5, 6, 10, 71, 149 and 150 of the Plans.
3. Revised the Recurring Special Provisions checklist.
4. Revised page ii of the Table of Contents to the Special Provisions.
5. Revised pages 14, 15, 16 and 17 of the Special Provisions.
6. Added pages 107 & 108 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 9; N. R. Stoner; Roger Driskell; R. E. Anderson; Estimates; Design & Environment File

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
F30021G3	SD-ACER RUBRUM 3GAL	EACH	192.000				
F30070G3	SD-FRAX PENN LAN 3GAL	EACH	192.000				
F30140G3	SD-QUERCUS MACR 3GAL	EACH	192.000				
F30150G3	SD-QUERCUS PALU 3GAL	EACH	192.000				
XX002154	MAN TA 4 DIA T3V F&G	EACH	5.000				
X0322729	MATL TRANSFER DEVICE	TON	12,624.000				
X0323080	DRAINAGE SCUPPR DS-12	EACH	7.000				
X0323092	HEADWALL REMOVAL	EACH	4.000				
X0325770	TRAF CONT-PROT SP C I	L SUM	1.000				
X0325771	TRAF CONT-PROT SP CII	L SUM	1.000				
X0325773	TRAF CONT-PROT SP C 3	L SUM	1.000				
* X0325804	MOD SOIL 18	SQ YD	8,713.000				
* X0325805	BIT SIDEWALK REM	SQ FT	8,000.000				
* X0488100	REM EX SEPTIC TANK	EACH	4.000				
X6020074	INLETS TA T3V F&G	EACH	56.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON - -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6020075	INLETS TB T3V F&G	EACH	4.000				
X7240205	REMOV SIGN COMPLETE	EACH	9.000				
X7330105	OSS WALKWAY TY A	FOOT	86.000				
X7340100	CONC FOUNDATION GR MT	CU YD	55.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0007603	BLDG REMOV NO 3	L SUM	1.000				
Z0007604	BLDG REMOV NO 4	L SUM	1.000				
Z0007605	BLDG REMOV NO 5	L SUM	1.000				
Z0007606	BLDG REMOV NO 6	L SUM	1.000				
Z0007607	BLDG REMOV NO 7	L SUM	1.000				
Z0007608	BLDG REMOV NO 8	L SUM	1.000				
Z0007609	BLDG REMOV NO 9	L SUM	1.000				
Z0007610	BLDG REMOV NO 10	L SUM	1.000				
Z0007611	BLDG REMOV NO 11	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON - -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
* Z0022800	FENCE REMOVAL	FOOT	1,500.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	6.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	1.000				
Z0041700	PLUG EX STORM SEWERS	EACH	11.000				
Z0049908	R&D NON-FR ASB BLD 8	L SUM	1.000				
Z0076600	TRAINEES	HOURL	2,000.000				
20100110	TREE REMOV 6-15	UNIT	80.000				
20100500	TREE REMOV ACRES	ACRE	18.000				
20200100	EARTH EXCAVATION	CU YD	99,195.000				
20400100	BORROW EXCAV	CU YD	426,655.000				
20700400	POROUS GRAN EMB SPEC	CU YD	496.000				
20800150	TRENCH BACKFILL	CU YD	627.900				
21101615	TOPSOIL F & P 4	SQ YD	68,779.000				
25000305	SEEDING CL 3A	ACRE	2.750				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON - -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000310	SEEDING CL 4	ACRE	8.500				
25000350	SEEDING CL 7	ACRE	41.200				
* 25000400	NITROGEN FERT NUTR	POUND	7,395.000				
* 25000500	PHOSPHORUS FERT NUTR	POUND	5,747.000				
* 25000600	POTASSIUM FERT NUTR	POUND	5,747.000				
* 25000700	AGR GROUND LIMESTONE	TON	102.300				
25000775	SELECT MOWING STAKES	EACH	104.000				
25001010	SEEDING CL 2 MOD	ACRE	43.200				
* 25100120	MULCH METHOD 2	TON	114.000				
25100630	EROSION CONTR BLANKET	SQ YD	27,036.000				
28000200	EARTH EXC - EROS CONT	CU YD	20.000				
28000250	TEMP EROS CONTR SEED	POUND	13,677.000				
28000300	TEMP DITCH CHECKS	EACH	194.000				
28000400	PERIMETER EROS BAR	FOOT	10,091.000				
28000500	INLET & PIPE PROTECT	EACH	108.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28001000	AGGREGATE - EROS CONT	TON	136.000				
28100705	STONE DUMP RIP CL A3	SQ YD	396.000				
28100707	STONE DUMP RIP CL A4	SQ YD	2,219.000				
28200200	FILTER FABRIC	SQ YD	2,934.000				
30200650	PROCESS MOD SOIL 12	SQ YD	62,106.000				
* DELETED							
30201500	LIME	TON	1,935.200				
31100100	SUB GRAN MAT A	TON	1,971.000				
31100910	SUB GRAN MAT A 12	SQ YD	19,252.000				
31101900	SUB GRAN MAT C	TON	4,227.000				
35100100	AGG BASE CSE A	TON	2,783.000				
40200700	AGG SURF CSE A 8	SQ YD	1,846.000				
40600100	BIT MATLS PR CT	GALLON	17,919.000				
40600300	AGG PR CT	TON	65.500				
40600625	LEV BIND MM N50	TON	37.000				
40603080	HMA BC IL-19.0 N50	TON	363.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40603095	HMA BC IL-19.0 N105	TON	15,166.000				
40603245	P HMA BC IL19.0 N105	TON	4,302.000				
40603335	HMA SC "D" N50	TON	214.000				
40603550	P HMA SC "D" N105	TON	1,806.000				
40603575	P HMA SC "E" N105	TON	1,686.000				
40701926	HMA PAVT FD 12 1/4	SQ YD	2,924.000				
42000311	PCC PVT 8 1/2 JOINTD	SQ YD	5,961.000				
42000411	PCC PVT 9 1/2 JOINTD	SQ YD	22,986.000				
42001200	PAVEMENT FABRIC	SQ YD	22,986.000				
42001300	PROTECTIVE COAT	SQ YD	41,005.000				
42001400	BR APPROACH PAVT SPL	SQ YD	593.000				
42400100	PC CONC SIDEWALK 4	SQ FT	17,745.000				
42400800	DETECTABLE WARNINGS	SQ FT	256.000				
44000100	PAVEMENT REM	SQ YD	14,481.000				
44000198	HMA SURF REM VAR DP	SQ YD	189.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000500	COMB CURB GUTTER REM	FOOT	6,481.000				
* 44000600	SIDEWALK REM	SQ FT	801.000				
44004000	PAVED DITCH REMOVAL	FOOT	882.000				
44004250	PAVED SHLD REMOVAL	SQ YD	18,840.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	72.000				
48101600	AGGREGATE SHLDS B 8	SQ YD	3,159.000				
48203021	HMA SHOULDERS 6	SQ YD	375.000				
48203029	HMA SHOULDERS 8	SQ YD	13,929.000				
50104400	CONC HDWL REM	EACH	2.000				
50105220	PIPE CULVERT REMOV	FOOT	443.000				
50200100	STRUCTURE EXCAVATION	CU YD	576.000				
50300100	FLOOR DRAINS	EACH	4.000				
50300225	CONC STRUCT	CU YD	285.800				
50300255	CONC SUP-STR	CU YD	814.500				
50300260	BR DECK GROOVING	SQ YD	1,387.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300280	CONCRETE ENCASEMENT	CU YD	8.400				
50300300	PROTECTIVE COAT	SQ YD	2,853.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	5,280.000				
50800105	REINFORCEMENT BARS	POUND	6,818.000				
50800205	REINF BARS, EPOXY CTD	POUND	269,410.000				
50800515	BAR SPLICERS	EACH	174.000				
50901730	BRIDGE FENCE RAILING	FOOT	260.000				
50901750	PARAPET RAILING	FOOT	260.000				
51100100	SLOPE WALL 4	SQ YD	971.000				
51201710	FUR STL PILE HP12X84	FOOT	990.000				
51202305	DRIVING PILES	FOOT	990.000				
51203710	TEST PILE ST HP12X84	EACH	2.000				
51204650	PILE SHOES	EACH	24.000				
51500100	NAME PLATES	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51603000	DRILLED SHAFT IN SOIL	CU YD	68.400				
51604000	DRILLED SHAFT IN ROCK	CU YD	16.300				
54001000	BOX CUL END SECT	EACH	3.000				
54010402	PCBC 4X2	FOOT	4.000				
54010603	PCBC 6X3	FOOT	53.000				
542A0229	P CUL CL A 1 24	FOOT	12.000				
542A3379	P CUL CL A 5 24	FOOT	156.000				
542A5491	P CUL CL A 1 EQRS 36	FOOT	43.000				
542JA024	P CUL CL A 24 JKD	FOOT	230.000				
54201291	P CUL 2 RCCP 36	FOOT	115.000				
54201303	P CUL 2 RCCP 48	FOOT	253.000				
54202143	P CUL 3 RCCP 48	FOOT	166.000				
54204219	P CUL 6 RCCP 24	FOOT	227.000				
54204231	P CUL 6 RCCP 36	FOOT	480.000				
5421C012	P CUL CL C 1 12 TEMP	FOOT	140.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54213657	PRC FLAR END SEC 12	EACH	8.000				
54213663	PRC FLAR END SEC 18	EACH	1.000				
54213669	PRC FLAR END SEC 24	EACH	11.000				
54213675	PRC FLAR END SEC 30	EACH	2.000				
54213681	PRC FLAR END SEC 36	EACH	6.000				
54213693	PRC FLAR END SEC 48	EACH	6.000				
54214731	PRCF END S EL EQRS 36	EACH	2.000				
54215547	MET END SEC 12	EACH	25.000				
54244405	FL INLT BX MED 542546	EACH	1.000				
54248510	CONCRETE COLLAR	CU YD	20.240				
550A0050	STORM SEW CL A 1 12	FOOT	853.000				
550A0070	STORM SEW CL A 1 15	FOOT	69.000				
550A0090	STORM SEW CL A 1 18	FOOT	424.000				
550A0120	STORM SEW CL A 1 24	FOOT	378.000				
550A0140	STORM SEW CL A 1 30	FOOT	134.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON - -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55100500	STORM SEWER REM 12	FOOT	261.000				
55100700	STORM SEWER REM 15	FOOT	39.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	187.000				
60100060	CONC HDWL FOR P DRAIN	EACH	59.000				
60100945	PIPE DRAINS 12	FOOT	1,616.000				
60107600	PIPE UNDERDRAINS 4	FOOT	27,380.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	821.000				
60109580	P UNDR FOR STRUCT 4	FOOT	311.000				
60221100	MAN TA 5 DIA T1F CL	EACH	2.000				
60221200	MAN TA 5 DIA T3F&G	EACH	3.000				
60223800	MAN TA 6 DIA T1F CL	EACH	1.000				
60235700	INLETS TA T3F&G	EACH	8.000				
60240220	INLETS TB T3F&G	EACH	1.000				
60255800	MAN ADJ NEW T1F CL	EACH	7.000				
60260500	INLETS ADJ NEW T3F&G	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON - -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60500040	REMOV MANHOLES	EACH	3.000				
60500060	REMOV INLETS	EACH	22.000				
60603500	COMB CC&G TB6.06	FOOT	852.000				
60603800	COMB CC&G TB6.12	FOOT	2,534.000				
60604400	COMB CC&G TB6.18	FOOT	1,169.000				
60605000	COMB CC&G TB6.24	FOOT	11,070.000				
60608600	COMB CC&G TM6.06	FOOT	94.000				
60610400	COMB CC&G TM6.24	FOOT	153.000				
60618300	CONC MEDIAN SURF 4	SQ FT	25,215.000				
60619121	CONC MED TSB-6	SQ FT	11,502.000				
60900515	CONC THRUST BLOCKS	EACH	50.000				
63000000	SPBGR TY A	FOOT	1,439.000				
63100045	TRAF BAR TERM T2	EACH	4.000				
63100085	TRAF BAR TERM T6	EACH	2.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON - -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63500105	DELINEATORS	EACH	160.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	27,874.000				
66400105	CH LK FENCE 4	FOOT	10,065.000				
66410300	CH LK FENCE REMOV	FOOT	5,543.000				
66700095	PERM SURV MKRS	EACH	6.000				
67000400	ENGR FIELD OFFICE A	CAL MO	18.000				
67100100	MOBILIZATION	L SUM	1.000				
* 67201000	SEAL ABAN WATER WELLS	EACH	4.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70101830	TRAF CONT-PROT BLR 21	L SUM	1.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	21.000				
70300725	TEMP PT PAVT MK 4 WH	FOOT	26,625.000				
70300825	TEMP PT PVT MK 4 YEL	FOOT	11,520.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70400100	TEMP CONC BARRIER	FOOT	14,025.000				
70400200	REL TEMP CONC BARRIER	FOOT	337.500				
72000300	SIGN PANEL T3	SQ FT	4,272.000				
72400800	REMOV SIGN COMPLETE	SQ FT	9.000				
72400900	REMOV SIGN PANEL	EACH	2.000				
72700100	STR STL SIN SUP BA	POUND	27,508.000				
73300100	OVHD SIN STR-SPAN T1A	FOOT	173.000				
73400100	CONC FOUNDATION	CU YD	74.000				
73700200	REM CONC FDN-GR MT	EACH	21.000				
78000200	THPL PVT MK LINE 4	FOOT	16,498.000				
78000400	THPL PVT MK LINE 6	FOOT	232.000				
78000600	THPL PVT MK LINE 12	FOOT	132.000				
78000650	THPL PVT MK LINE 24	FOOT	105.000				
78004210	PREF PL PM TB INL L4	FOOT	21,828.000				
78004240	PREF PL PM TB INL L8	FOOT	4,006.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78004250	PREF PL PM TB INL L12	FOOT	281.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	619.000				
78008220	POLYUREA PM T1 LN 5	FOOT	9,949.000				
78008230	POLYUREA PM T1 LN 6	FOOT	2,534.000				
78008250	POLYUREA PM T1 LN 12	FOOT	531.000				
78008270	POLYUREA PM T1 LN 24	FOOT	371.000				
78100100	RAISED REFL PAVT MKR	EACH	731.000				
78200405	GUARDRAIL MARKERS	EACH	18.000				
78201000	TERMINAL MARKER - DA	EACH	6.000				
78300100	PAVT MARKING REMOVAL	SQ FT	19,385.000				
78300200	RAISED REF PVT MK REM	EACH	419.000				
80400100	ELECT SERV INSTALL	EACH	1.000				
81021550	CON AUGERED 2 PVC	FOOT	710.000				
81603035	UD 2#6 #6G XLPUSE 1	FOOT	12,035.000				
81900200	TR & BKFIL F ELECT WK	FOOT	10,915.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 98963

State Job # - C-99-028-06
 PPS NBR - 9-81370-0100
 County Name - JEFFERSON- -
 Code - 81 - -
 District - 9 - -
 Section Number - (41-3)HBK

Project Number
 HPD-F-0520/001/

Route
 FAI 57/64

* REVISED : JUNE 1, 2007

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
82102400	LUM SV HOR MT 400W	EACH	41.000				
82500540	LT CONT CBRCS 100-480	EACH	1.000				
83010600	LT P A 50MH 15MA	EACH	41.000				
83600300	LIGHT POLE FDN 30D	FOOT	287.000				
83800205	BKWY DEV TR B 15BC	EACH	41.000				

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

<u>CHECK SHEET #</u>	<u>PAGE NO.</u>
1 X Additional State Requirements For Federal-Aid Construction Contracts (Eff. 2-1-69) (Rev. 1-1-07).....	1
2 X Subletting of Contracts (Federal-Aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93)	3
3 X EEO (Eff. 7-21-78) (Rev. 11-18-80)	4
4 Specific Equal Employment Opportunity Responsibilities Non Federal-Aid Contracts (Eff. 3-20-69) (Rev. 1-1-94)	14
5 Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1-1-07)	19
6 Reserved	24
7 X National Pollutant Discharge Elimination System Permit (Eff. 7-1-94) (Rev. 1-1-03).....	25
8 Haul Road Stream Crossings, Other Temporary Stream Crossings, and In-Stream Work Pads (Eff. 1-2-92) (Rev. 1-1-98).....	26
9 Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-07).....	27
10 X Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-07)	30
11 Use of Geotextile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-07).....	33
12 Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 1-1-07).....	35
13 X Hot-Mix Asphalt Surface Removal (Cold Milling) (Eff. 11-1-87) (Rev. 1-1-07)	39
14 Pavement and Shoulder Resurfacing (Eff. 2-1-00) (Rev. 1-1-07)	41
15 PCC Partial Depth Hot-Mix Asphalt Patching (Eff. 1-1-98) (Rev. 1-1-07)	42
16 Patching with Hot-Mix Asphalt Overlay Removal (Eff. 10-1-95) (Rev. 1-1-07).....	44
17 Polymer Concrete (Eff. 8-1-95) (Rev. 3-1-05)	45
18 PVC Pipeliner (Eff. 4-1-04) (Rev. 1-1-07)	47
19 X Pipe Underdrains (Eff. 9-9-87) (Rev. 1-1-07)	48
20 X Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97)	49
21 Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-07)	53
22 Temporary Modular Glare Screen System (Eff. 1-1-00) (Rev. 1-1-07)	55
23 Temporary Portable Bridge Traffic Signals (Eff. 8-1-03) (Rev. 1-1-07)	57
24 X Work Zone Public Information Signs (Eff. 9-1-02) (Rev. 1-1-07).....	59
25 X Night Time Inspection of Roadway Lighting (Eff. 5-1-96).....	60
26 English Substitution of Metric Bolts (Eff. 7-1-96).....	61
27 English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03).....	62
28 Calcium Chloride Accelerator for Portland Cement Concrete (Eff. 1-1-01)	63
29 Quality Control of Concrete Mixtures at the Plant-Single A (Eff. 8-1-00) (Rev. 1-1-04)	64
30 Quality Control of Concrete Mixtures at the Plant-Double A (Eff. 8-1-00) (Rev. 1-1-04)	70
31 Quality Control/Quality Assurance of Concrete Mixtures (Eff. 4-1-92) (Rev. 1-1-07).....	78

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

<u>CHECK SHEET #</u>	<u>PAGE NO.</u>
1 X Additional State Requirements For Federal-Aid Construction Contracts (Eff. 2-1-69) (Rev. 1-1-07).....	1
2 X Subletting of Contracts (Federal-Aid Contracts) (Eff. 1-1-88) (Rev. 5-1-93)	3
3 X EEO (Eff. 7-21-78) (Rev. 11-18-80)	4
4 Specific Equal Employment Opportunity Responsibilities Non Federal-Aid Contracts (Eff. 3-20-69) (Rev. 1-1-94)	14
5 Required Provisions - State Contracts (Eff. 4-1-65) (Rev. 1-1-07)	19
6 Reserved	24
7 X National Pollutant Discharge Elimination System Permit (Eff. 7-1-94) (Rev. 1-1-03).....	25
8 Haul Road Stream Crossings, Other Temporary Stream Crossings, and In-Stream Work Pads (Eff. 1-2-92) (Rev. 1-1-98).....	26
9 Construction Layout Stakes Except for Bridges (Eff. 1-1-99) (Rev. 1-1-07).....	27
10 X Construction Layout Stakes (Eff. 5-1-93) (Rev. 1-1-07)	30
11 Use of Geotextile Fabric for Railroad Crossing (Eff. 1-1-95) (Rev. 1-1-07).....	33
12 Subsealing of Concrete Pavements (Eff. 11-1-84) (Rev. 1-1-07).....	35
13 X Hot-Mix Asphalt Surface Removal (Cold Milling) (Eff. 11-1-87) (Rev. 1-1-07)	39
14 Pavement and Shoulder Resurfacing (Eff. 2-1-00) (Rev. 1-1-07)	41
15 PCC Partial Depth Hot-Mix Asphalt Patching (Eff. 1-1-98) (Rev. 1-1-07)	42
16 Patching with Hot-Mix Asphalt Overlay Removal (Eff. 10-1-95) (Rev. 1-1-07).....	44
17 Polymer Concrete (Eff. 8-1-95) (Rev. 3-1-05)	45
18 PVC Pipeliner (Eff. 4-1-04) (Rev. 1-1-07)	47
19 X Pipe Underdrains (Eff. 9-9-87) (Rev. 1-1-07)	48
20 X Guardrail and Barrier Wall Delineation (Eff. 12-15-93) (Rev. 1-1-97)	49
21 Bicycle Racks (Eff. 4-1-94) (Rev. 1-1-07)	53
22 Temporary Modular Glare Screen System (Eff. 1-1-00) (Rev. 1-1-07)	55
23 Temporary Portable Bridge Traffic Signals (Eff. 8-1-03) (Rev. 1-1-07)	57
24 X Work Zone Public Information Signs (Eff. 9-1-02) (Rev. 1-1-07).....	59
25 X Night Time Inspection of Roadway Lighting (Eff. 5-1-96).....	60
26 English Substitution of Metric Bolts (Eff. 7-1-96).....	61
27 English Substitution of Metric Reinforcement Bars (Eff. 4-1-96) (Rev. 1-1-03).....	62
28 Calcium Chloride Accelerator for Portland Cement Concrete (Eff. 1-1-01)	63
29 Quality Control of Concrete Mixtures at the Plant-Single A (Eff. 8-1-00) (Rev. 1-1-04)	64
30 Quality Control of Concrete Mixtures at the Plant-Double A (Eff. 8-1-00) (Rev. 1-1-04)	70
31 Quality Control/Quality Assurance of Concrete Mixtures (Eff. 4-1-92) (Rev. 1-1-07).....	78

BUILDING REMOVAL - CASE III (FRIABLE ASBESTOS ABATEMENT) (BDE) 44

CEMENT (BDE) 48

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 50

EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 57

ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE)..... 58

HOT-MIX ASPHALT EQUIPMENT, SPREADING AND FINISHING MACHINE (BDE) 60

IMPACT ATTENUATORS, TEMPORARY (BDE)..... 60

MATERIAL TRANSFER DEVICE (BDE) 62

PAYMENTS TO SUBCONTRACTORS (BDE) 63

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) 64

POLYUREA PAVEMENT MARKING (BDE)..... 64

PRECAST CONCRETE HANDLING HOLES (BDE) 71

PUBLIC CONVENIENCE AND SAFETY (BDE) 72

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 73

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 78

REINFORCEMENT BARS (BDE) 79

SEEDING (BDE) 81

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 82

STEEL PLATE BEAM GUARDRAIL (BDE) 83

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 84

SURFACE TESTING OF PAVEMENTS (BDE) 84

TEMPORARY EROSION CONTROL (BDE) 90

THERMOPLASTIC PAVEMENT MARKINGS (BDE) 91

TRAINING SPECIAL PROVISIONS 92

TYPE ZZ RETROREFLECTIVE SHEETING, NONREFLECTIVE SHEETING, AND TRANSLUCENT
 OVERLAY FILM FOR HIGHWAY SIGNS (BDE) 94

VARIABLY SPACED TINING (BDE)..... 99

WORKING DAYS (BDE) 99

EXPIRATION/RENEWAL OF 404 PERMITS 100

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 100

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 103

SEALING ABANDONED WATER WELLS 107

REMOVING EXISTING SEPTIC TANK 107

BITUMINOUS SIDEWALK REMOVAL 108

FENCE REMOVAL 108

Revised 06/01/2007

Seed Mixture	Spring 3/1 to 6/1 Lbs./Acre	Fall 8/1 to 10/1 Lbs./Acre	Dormant 11/15 to 3/1 Lbs./Acre
Perennial Ryegrass	20	20	20
Wild Rye (Elymus Canadensis)	20	20	20
Switchgrass (Panicum virgatum)	10	10	10
Little Bluestem (Andropogon scoparius)	12	12	12
Side-Oats Grama (Bouteloua curtipendula)	10	10	10
White Prairie Clover (Petalostemum candidum)	5	5	5
Black-Eyed Susan (Rudbeckia hirta)	5	5	5
Spring Oats	50	50	50

(b) Fertilizer and agricultural ground limestone shall be uniformly spread over the designated areas immediately prior to seed bed preparation at the following rates per acre:

- 120 lb. of Nitrogen Fertilizer Nutrients
- 120 lb. of Phosphorus Fertilizer Nutrients
- 120 lb. of Potassium Fertilizer Nutrients

2 tons of Agricultural Ground Limestone

(c) Straw mulch shall be applied to all seeded areas at the rate of 2 tons per acre of Method 2.

(d) Erosion Control Blanket shall be used:

- 3. In place of straw mulch in ditch flow-lines.
- 4. In place of straw mulch on slopes steeper than 3:1.

Basis of Payment. This work shall be paid for at the contract unit price per acre for SEEDING CLASS 3A; at the contract unit price per pound for NITROGEN FERTILIZER NUTRIENT, PHOSPHORUS FERTILIZER NUTRIENT, AND POTASSIUM FERTILIZER NUTRIENT; at the contract unit price per ton for AGRICULTURAL GROUND LIMESTONE; at the contract unit price per acre for MULCH, METHOD 2; and at the contract unit price per square yard for EROSION CONTROL BLANKET.

CLASS 4 (NATIVE GRASS) SEEDING AND MULCH

This work shall be performed in accordance with Sections 250 and 251 of the Standard Specifications, as shown in the plans, and as follows:

(a) Class 4 Seeding (Native Grass) shall be used at the locations shown in the plans. The following seed mixture and rates per acre shall be used during the time of year indicated:

Revised 06/01/2007

Seed Mixture	Spring March 1 to June 14 Lb/Acre	Summer/ Fall June 15 to Oct. 14 lbs./acre	Dormant Oct. 15 to Feb. 28 Lb/Acre
Andropogon gerrardii (Big Bluestem)	4		6
Andropogon scoparius (Little Bluestem)	5	DO	7.5
Bouteloua curtipendula (Side oats Grama)	5	NOT	7.5
Elymus Canadensis (Wild Rye)	1	SEED	1.5
Panicum virgatum (Switch grass)	1		1.5
Sorghastrum nutans (Indian grass)	2		3
Annual Ryegrass	25		45
Oats, Spring	25		45
Perennial Ryegrass	15		22.5

(b) Fertilizer and agricultural ground limestone shall be uniformly spread over the designated areas immediately prior to seed bed preparation at the following rates per acre:

120 lbs. of Nitrogen Fertilizer Nutrients
 120 lbs. of Phosphorus Fertilizer Nutrients
 120 lbs. of Potassium Fertilizer Nutrients

2 tons of Agricultural Ground Limestone

(c) Straw mulch shall be applied to all bare earth seeded areas at the rate of 2 tons per acre of Method 2

(d) Selective Mowing Stakes (Art. 250.08) shall be installed at 50 foot spacing around the perimeter of the Class 4 seeded areas. The top 10 inches of the steel post shall be painted with two coats of white paint (see Art. 1081.13) over green paint on the steel posts.

Basis of Payment. This work shall be paid for at the contract unit price per acre for SEEDING CLASS 4 (Native Grass); at the contract unit price per acre for MULCH METHOD 2, and for the contract unit price each for SELECTIVE MOWING STAKES.

Revised 06/01/2007

REMOVE SIGN COMPLETE AND REMOVE SIGN PANEL

This work shall consist of removing the sign panels and breakaway sign support as shown on the signing sheets. The materials shall be delivered to the District 9 IDOT Sign Shop at the Carbondale office. The contractor will be responsible for any damaged or stolen materials until delivered to the above location.

This work will be paid for at the contract unit price each for REMOVE SIGN COMPLETE or REMOVE SIGN PANEL of the type specified.

MODIFIED SOIL, 18”

The following locations were identified as poorly draining and seasonally containing excessive moisture and low strength which may prevent suitable preparation of the subgrade for embankment construction:

Ramp A	Station 300+00 to 311+00
Ramp B	Station 412+00 to 421+50
Ramp C	Station 500+00 to 504+00

In addition to the requirements of Article 301 of the Standard Specifications the contractor shall prepare the embankment subgrade at locations determined by the Engineer in accordance with Section 302 except as modified herein:

For Article 302.02 delete (a), (b), (g), (h), and (j).

Add the following to the end of Article 302.03:

Other equipment meeting the approval of the Engineer may be used to mix the modifier with the soil, provided mixing is adequate to dry the subgrade soil sufficiently to provide a stable working platform.

Replace Article 302.05 with the following:

The modifier shall be applied at a rate of 100 lbs. dry lime per square yard. The Engineer may reduce the rate of application as field conditions warrant.

Replace Article 302.08 with the following:

The modifier, soil, and water shall be mixed to the satisfaction of the Engineer to a depth of eighteen (18) inches.

Delete Article 302.10

Revised 06/01/2007

Replace Article 302.13 with the following:

This work will be paid for at the contract unit price per square yard for MODIFIED SOIL, 18" and per ton for LIME.

REMOVAL OF UNSTABLE SOILS

The following locations were identified as containing material that will not provide a stable platform for paving operations:

Ramp B	Station 412+50 to 413+50	(Transition from cut to fill)
Ramp C	Station 512+00 to 517+00	(Fill in existing ditch)
Ramp D	Station 602+00 to 604+00	(Fill in existing ditch)
Ramp D	Station 610+00 to 611+00	(Transition from cut to fill)
I-57/64 NB	Station 701+00 to 704+00	(Existing outside shoulder)
I-57/64 SB	Station 738+00 to 740+00	(Existing inside shoulder)

These areas shall be undercut 18" to stable material as determined by the Engineer. The excavated soils shall be replaced with aggregate, suitable borrow or earth excavation. The material placed in the undercuts is considered part of the embankment and shall be placed and compacted in accordance with the requirements of Article 205 of the Standard Specifications.

The excavated undercut material may be used elsewhere in the embankment subject to the following restrictions: 1) the placement location of the undercut soils must be approved by the Engineer, and 2) the moisture content of the undercut material must be reduced by thorough disking to not more than 110% of Standard Proctor Optimum.

Excavation of the undercut material will be paid for at the contract unit price for Earth Excavation. No additional compensation will be allowed for the additional drying and/or haul distance required to meet the requirements of this Special Provision.

The undercut location listed above is approximate and may be increased or reduced by the Engineer as field conditions warrant.

RESTRICTED EARTH EXCAVATION

The top 18" of materials to be removed in the southeast and southwest infields of the intersection as shown on page 190 of the plans should be removed are considered "restricted."

These "restricted" materials must be placed within the embankment core and will not be allowed within 2.0 feet of the proposed subgrade or within 10 feet horizontally of the proposed side slopes.

The actual limits of "restricted" material will be determined by the Engineer as excavation progresses.

Revised 06/01/2007

SEALING ABANDONED WATER WELLS

The sealing of abandoned water wells shall be paid for according to Article 672.01 of the Standard Specifications at these locations.

<u>Parcel No.</u>	<u>Location</u>
7401217	11884 Ryegrass Lane Mt. Vernon, IL
7401213	11020 East Graham Rd Mt. Vernon, IL
7401208	12134 Starrett Lane Mt. Vernon, IL
7401219	11851 Ryegrass Lane Mt. Vernon, IL

REMOVING EXISTING SEPTIC TANK

Septic tanks to be removed shall be completely pumped by a licensed waste hauler. The removal of the septic tank shall also include backfilling of the excavated hole. Backfill shall be of select material approved by the engineer to an elevation 4" below existing grade. Compaction of the select material shall be to the satisfaction of the Engineer.

Location of existing septic tanks.

<u>Parcel No.</u>	<u>Location</u>
7401217	11884 Ryegrass Lane Mt. Vernon, IL
7401213	11020 East Graham Rd Mt. Vernon, IL
7401208	12134 Starrett Lane Mt. Vernon, IL
7401219	11851 Ryegrass Lane Mt. Vernon, IL

Added 06/01/2007

The septic system located on parcel no. 7401210 (East Graham Road) shall be removed and relocated by others per commitment with the City of Mt. Vernon and will not be included in this contract.

This work will be paid for at the contract unit price EACH for REMOVING EXISTING SEPTIC TANK.

BITUMINOUS SIDEWALK REMOVAL

This work includes the removal and disposal of all existing bituminous sidewalks, railroad ties, and any sub-base material at the locations shown in the plans or as directed by the Engineer.

Basis of Payment. This work shall be measured and paid for at the contract unit price per square foot for BITUMINOUS SIDEWALK REMOVAL.

FENCE REMOVAL

This work shall consist of the removal and disposal of the existing decorative fence located at 11884 Ryegrass Lane, Parcel No. 7401217(Mt. Vernon Dream Homes) as shown in the plans or as directed by the Engineer.

Basis of Payment. This work shall be measured and paid for at the contract unit price per foot for FENCE REMOVAL.

Added 06/01/2007