

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FED. / 20% STATE		100%		LIGHTING 90% FEDERAL 10% STATE <i>Y030-1E</i>	TRUSS SIGN PANELS 100% STATE <i>Y002-1C</i>
				ROADWAY J000-2A	BRIDGE X271-2A	ROADWAY FAI 57/64 90% FEDERAL 10% STATE			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	593	593					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	17745	17745					
42400800	DETECTABLE WARNINGS	SQ FT	256	256					
44000100	PAVEMENT REMOVAL	SQ YD	14481	12562		1919			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	189	189					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6481	6481					
44000600	SIDEWALK REMOVAL	SQ FT	801	201		600			
44004000	PAVED DITCH REMOVAL	FOOT	882			882			
44004250	PAVED SHOULDER REMOVAL	SQ YD	18840			18840			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	72	72					
48101600	AGGREGATE SHOULDERS, TYPE B, 8"	SQ YD	3159			3159			
48203021	HOT-MIX ASPHALT SHOULDERS 6"	SQ YD	375			375			
48203029	HOT-MIX ASPHALT SHOULDERS 8"	SQ YD	13929	1063		12866			
50104400	CONCRETE HEADWALL REMOVAL	EACH	2			2			
50105220	PIPE CULVERT REMOVAL	FOOT	443	443					
50200100	STRUCTURE EXCAVATION	CU YD	576		576				
50300100	FLOOR DRAINS	EACH	4		4				
50300225	CONCRETE STRUCTURES	CU YD	285.8		285.8				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	814.5		814.5				
50300260	BRIDGE DECK GROOVING	SQ YD	1387		1387				
50300280	CONCRETE ENCASEMENT	CU YD	8.4		8.4				
50300300	PROTECTIVE COAT	SQ YD	2853		2853				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1				
50500505	STUD SHEAR CONNECTORS	EACH	5280		5280				
50800105	REINFORCEMENT BARS	POUND	6818	1848	4970				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	269410		269410				
50800515	BAR SPLICERS	EACH	174		174				
50901750	PARAPET RAILING	FOOT	260		260				
50901730	BRIDGE FENCE RAILING	FOOT	260		260				
51100100	SLOPE WALL 4 INCH	SQ YD	971		971				
51201710	FURNISHING STEEL PILES HP12X84	FOOT	990		990				
51202305	DRIVING PILES	FOOT	990		990				
51203710	TEST PILE STEEL HP12X84	EACH	2		2				

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/27/2007 10:35 AM
 I:\981006\9820190\Road\S\head\C-601500.dgn

LAYOUT	RLT	02/26/04
DRAWN	JED	04/12/04
REVIEWED	MTM	03/22/07

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK SCALE: NO SCALE DATE 3-22-07
NAME	DATE	

Rev. 6-1-07