

SEEDING AND EROSION CONTROL SCHEDULE - RAMPS

LOCATION STATION TO STATION	SEEDING CLASS 2 (MODIFIED)	SEEDING CLASS 4	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	STONE DUMPED RIPRAP, CLASS A4	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	
	ACRE			ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	SQ YD	POUND	SQ YD	FOOT
I-57/I-64														
691+75 (RT 13')														1
691+98 (LT 106')														1
703+00 TO 713+00 (MEDIAN)	1.8		1.8	288	216	216	3.6	3.6	355.6	540				
706+26 TO 721+55 RT	3.4		3.4	544	408	408	6.8	6.8	955.6	1020				
711+09 TO 722+59 LT		5.4	5.4	648	480	480	10.8	10.8	1620					
711+47 TO 723+24 LT	3.0		3.0	480	360	360	6.0	6.0	1111.1	900				
721+19 TO 735+17 RT	3.6		3.6	576	432	432	7.2	7.2	1211.1	1080				
722+96 TO 73644 LT	3.0		3.0	480	360	360	6.0	6.0	900					
723+69 TO 734+77 LT		3.1	3.1	124				6.2	1045.0	930				
742+12 TO 756+00 RT	2.3		2.3	368	276	276	4.6	4.6	622.2	690				
741+00 TO 75800 LT	2.5		2.5	400	300	300	5.0	5.0	755.6	750				
749+00 (LT 27')														1
RAMP A														
301+00 TO 322+50 RT	2.9		2.9	464	348	348	5.8	5.8	950.2	870				
301+50 (56') TO 306+50 (36') LT												480		
301+50 (45') TO 306+50 (21') RT												516		
RAMP B														
400+00 TO 420+50 RT	3.4		3.4	544	408	408	6.8	6.8	911.1	1020				
411+00 (LT 30')											48.83			1
414+50 (23') TO 420+50 (42') RT												601		
414+50 (40') TO 420+50 (57') LT												601		
RAMP C														
501+00 TO 528+00 RT	4.2		4.2	672	504	504	8.4	8.4	1200.0	1260				
503+50 (LT 84')											13.33			1
501+00 (56') TO 508+50 (39') LT												728		
501+00 (45') TO 508+50 (23') RT												770		
RAMP D														
600+00 TO 616+75 RT	2.6		2.6	416	312	312	5.2	5.2	755.6	780				
611+50 (57') TO 616+50 (37') LT												501		
612+00 (23') TO 616+50 (39.5') RT												451		
VETERANS DRIVE														
43+42 (LT 78')											13.85			1
TOTALS	32.7	8.5	41.2	6220	4572	4572	70.2	93.2	9873	12360	76.0	4648	6	

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

6/22/2007 05:35 PM
 R:\9810\as98s2019\road\sheet\ac-613-sched.rpt

LA/011	RLT	02/26/04
DRWN	JED	04/12/04
RT/REV	MTM	03/27/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK
 SCALE: NO SCALE
 DATE 3-22-07
 DRAWN BY RLT
 CHECKED BY MTM

Rev. 5-31-07