

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	OX1-6-2HBK	WILLIAMSON	272	5
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A	X281-2A	Y080	STATE 100%
				FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2	2			
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	10	10			
60405800	GRATES AND COVERS, TYPE 2A	EACH	2	2			
60500050	REMOVING CATCH BASINS	EACH	1	1			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	16.0	16.0			
60602500	CONCRETE GUTTER, TYPE A	FOOT	314	314			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,651	2,651			
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	882	882			
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	42	42			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3,708	3,708			
60625900	P. C. C. RAMPED MEDIAN TERMINAL	EACH	2	2			
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,025	1,025			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	1	1			
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	7	7			
* 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	515	515			
63500105	DELINEATORS	EACH	145	145			
63500120	DELINEATOR REMOVAL	EACH	45	45			
66400105	CHAIN LINK FENCE, 4'	FOOT	3,459	3,459			
66500105	WOVEN WIRE FENCE, 4'	FOOT	490	490			
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	3,137	3,137			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	21	21			
66700095	PERMANENT SURVEY MARKERS	EACH	6	6			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12			
67100100	MOBILIZATION	L SUM	1	1			
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1			
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1			
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1			
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	180	180			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	512	512			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8	72.8			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13,454	13,454			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,261	1,261			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	193	193			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	40	40			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,892.0	2,892.0			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,707	2,707			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	921	921			

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 MORGAN AVENUE INTERCHANGE
 FAI ROUTE 57 WITH FAU ROUTE 9718
 WILLIAMSON COUNTY
 3 OF 5
 SCALE: N/A
 DATE: 5-04-2007
 DRAWN BY: DH
 CHECKED BY: RD

PLOT DATE = 5/4/2007
 FILE NAME = P:\98994\98994.dgn
 PLOT SCALE = 50.0000' / IN.
 USER NAME = dthorne

Rev.