

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 938	05-00064-00-RS	PULASKI	32	3
PROJECT NO. RS-HPP-3300 (002)			CONTRACT NO. 99260	

PAINT PAVEMENT MARKING - LINE 4"		
Centerline (Yellow Dashed)	Edge Line (White Solid)	No Passing (Yellow Solid)
8,000 Ft.	78,199 Ft.	27,141 Ft.

NOTE: Any bridges that are omitted shall receive pavement marking.

"NO PASSING ZONES"			
EAST BOUND LANE		WEST BOUND LANE	
Location	Length	Location	Length
Sta. 102+50 ¹ to Sta. 110+50	800'	Sta. 112+50 to Sta. 119+25 ¹	675'
Sta. 128+00 ¹ to Sta. 138+25	825'	Sta. 137+00 to Sta. 145+00 ¹	800'
Sta. 146+75 ¹ to Sta. 154+75	800'	Sta. 155+75 to Sta. 163+75 ¹	800'
Sta. 195+50 ¹ to Sta. 202+50	700'	Sta. 204+50 to Sta. 211+50 ¹	700'
Sta. 211+75 ¹ to Sta. 220+50	875'	Sta. 220+50 to Sta. 229+50 ¹	900'
Sta. 241+00 ¹ to Sta. 245+50	450'	Sta. 250+00 to Sta. 254+50 ¹	450'
Sta. 267+75 ¹ to Sta. 273+25	550'	Sta. 276+75 to Sta. 282+25 ¹	550'
Sta. 340+00 ¹ to Sta. 370+25	3,025'	Sta. 349+00 to Sta. 381+50 ¹	3,020'
Sta. 379+50 ¹ to Sta. 385+25	575'	Sta. 388+25 to Sta. 394+00 ¹	575'
Sta. 392+00 ¹ to Sta. 397+50	550'	Sta. 400+75 to Sta. 406+00 ¹	525'
Sta. 409+00 ¹ to Sta. 414+00	500'	Sta. 417+00 to Sta. 422+75 ¹	575'
Sta. 421+75 ¹ to Sta. 480+12	5,728'	Sta. 432+00 to Sta. 480+12	4,703'
TOTALS	15,378'		14,273'

¹ Denotes location of "No Passing Zone" signs to be erected in accordance with Sign Schedule & Std. 720006.

HMA SURFACE REMOVAL 2"	
Bridge Location	Area (S.Y.)
Sta. 308+73.6 to Sta. 309+76.6	344
Sta. 331+43.5 to Sta. 332+16.5	244
TOTAL	588

HMA SURF. REMOVAL - BUTT JT.	
Location	Area (S.Y.)
Sta. 83+43.4 to Sta. 83+80.0	86
Sta. 307+98.6 to Sta. 308+73.6	183
Sta. 309+76.6 to Sta. 310+51.6	183
Sta. 330+68.5 to Sta. 331+43.5	183
Sta. 332+16.5 to Sta. 332+91.5	183
Sta. 479+87.2 to Sta. 480+12.2	418
TOTAL	1,236

SIGNS				
Location	Name	Signs No.	Sq. Ft.	Post Length
Sta. 156+70 Lt.	SIDE ROAD 90'	W2-2	9.00	16.5
Sta. 222+30 Lt.	CROSS ROAD	W2-1	9.00	16.5
Sta. 277+10 Lt.	SIDE ROAD 90'	W2-2	9.00	16.5
Sta. 441+40 Rt.	STOP	R1-1	9.00	16.5
	DO NOT ENTER	R5-1	9.00	-
Sta. 442+00 Rt.	STOP	R1-1	9.00	16.5
	DO NOT ENTER	R5-1	9.00	-
Sta. 474+00 Rt.	STOP AHEAD	W3-1a	9.00	16.5
Sta. 479+91 Rt.	STOP	R1-1	9.00	15.5
Various (23)*	NO PASSING	W14-3	227.70	759.0
TOTALS			308.70	873.5

* See schedule of "No Passing Zones" for sign locations. Each location will have one sign of 9.90 Sq. Ft. and two posts with a combined length of 33.0 Ft. Quantities shown are totals.

THERMOPLASTIC PAVEMENT MARKING					
Location	Description	Sym. & Ltrs. Sq. Ft.	Line 4" Foot	Line 12" Foot	Line 24" Foot
Sta. 434+68 - 440+88 Rt.	Flush Median		2,484	178	
Sta. 439+08 - 440+24 Rt.	Lane Line		116		
Sta. 439+15 Rt.	"ONLY"	20.8			
Sta. 439+45 Rt.	Through Arrow	11.5			
Sta. 439+75 Rt.	Right Arrow	15.6			
Sta. 440+65 Rt.	Flush Island		168	73	
Sta. 441+23 Rt.	Flush Island		66	31	
Sta. 441+49 - 442+83 Rt.	Lane Line		134		
Sta. 441+51	Stop Bar				30
Sta. 441+58 - 442+83 Rt.	No Passing		250		
Sta. 441+67 Rt.	Flush Island		82	20	
Sta. 441+83 Rt.	Stop Bar				26
Sta. 442+16 Rt.	Left Arrow	15.6			
Sta. 442+46 Lt.	Through Arrow	11.5			
Sta. 442+76 Rt.	"ONLY"	20.8			
Sta. 442+83 - 447+23 Rt.	Flush Median		1,760	93	
Sta. 479+68 Rt.	Stop Bar				35
Sta. 479+90 Rt.	Stop Bar				23
TOTALS		95.8	5,060	395	114