

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 938	05-00064-00-RS	PULASKI	32	4
PROJECT NO. RS-HPP-3300 (002)			CONTRACT NO. 99260	

RESURFACING SCHEDULE

Location Station to Station	Length Feet	Prime Coat		Leveling Binder Machine Method Tons	Hot-Mix Asphalt Binder Course Tons	Hot-Mix Asphalt Surface Course Tons
		Bituminous Materials Gallons	Aggregate Tons			
EASTBOUND (RIGHT) LANE						
83+20 to 89+50	630.00	20.6	0.3		85.8	76.5
89+50 to 298+00	20850.00	477.2	7.2		3733.6	2566.8
298+00 to 308+73.60	1073.60	32.2	0.4		269.7	151.2
308+73.60 to 309+76.60	103.00	17.7	0.3			19.8
309+76.60 to 331+43.50	2166.90	64.7	1.0		629.7	305.1
331+43.50 to 332+16.50	73.00	12.5	0.2			14.0
332+16.50 to 343+26	1099.50	32.8	0.5		201.4	154.9
343+26 to 344+62.30	136.30	3.1			18.3	19.2
344+62.30 to 358+66	1403.70	32.1	0.5	174.4	1.3	197.6
358+66 to 372+79.06	1413.06	32.4	0.5	142.4	1.7	199.0
372+79.06 to 374+15	135.94	3.1			22.2	19.1
374+15 to 413+24	3678.96	84.2	1.3		786.1	518.0
413+24 to 419+71	647.00	14.8	0.2		141.9	91.1
419+71 to 434+68	1497.00	34.3	0.5		267.3	210.8
434+68 to 447+23	1255.00	28.7	0.5		272.1	176.7
447+23 to 464+45	1628.80	37.3	0.5		293.9	229.3
464+45 to 472+24.65	779.65	17.8	0.3		168.8	109.8
472+24.65 to 480+12.23	771.58	114.8	1.7		4.2	92.1
Subtotals for EastBound (Right) Lane		1060.3	15.9	316.8	6898.0	5151.0
WESTBOUND (LEFT) LANE						
83+20 to 89+50	630.00	20.6	0.3		105.9	76.5
89+50 to 298+00	20850.00	477.2	7.2		3053.5	2566.8
298+00 to 308+73.60	1073.60	32.2	0.4		195.9	151.2
308+73.60 to 309+76.60	103.00	17.7	0.3			19.8
309+76.60 to 331+43.50	2166.90	64.7	1.0		395.9	305.1
331+43.50 to 332+16.50	73.00	12.5	0.2			14.0
332+16.50 to 343+26	1099.50	32.8	0.5		207.8	154.9
343+26 to 344+62.30	136.30	3.1			27.4	19.2
344+62.30 to 358+66	1403.70	32.1	0.5	144.3	2.1	197.6
358+66 to 372+79.06	1413.06	32.4	0.5	162.2	2.4	199.0
372+79.06 to 374+15	135.94	3.1			33.8	19.1
374+15 to 413+24	3678.96	84.2	1.3		886.4	518.0
413+24 to 419+71	647.00	14.8	0.2		137.0	91.1
419+71 to 434+68	1497.00	34.3	0.5		386.5	210.8
434+68 to 447+23	1255.00	28.7	0.5		243.3	176.7
447+23 to 464+45	1628.80	37.3	0.5		355.6	229.3
464+45 to 472+24.65	779.65	17.8	0.3		147.1	109.8
472+24.65 to 480+12.23	771.58	114.8	1.7		5.4	80.5
Subtotals for WestBound (Left) Lane		1060.3	15.9	306.5	6186.0	5139.4
TOTALS		2120.6	31.8	623.3	13084.0	10290.4

NOTE: Quantities shown do not include materials for entrances, side roads, and mailbox turnouts.