

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 931	99-00038-01-RS	JOHNSON	5	3
PROJECT NO. RS-931 (10B)			CONTRACT NO. 99279	

RESURFACING SCHEDULE

Location Station to Station	Length (For information only) Feet	Prime Coat		Leveling Binder Machine Method Tons	Hot-Mix Asphalt Binder Course Tons	Hot-Mix Asphalt Surface Course Tons
		Bituminous Materials Gallons	Aggregate Tons			
		SOUTHBOUND (RIGHT) LANE				
0+00 to 6+66	666.00	18.9	0.3	59.1		53.6
6+66 to 15+62	896.00	20.5	0.3	57.9	102.4	72.0
15+62 to 26+40	1078.00	24.7	0.4	128.2		86.7
26+40 to 34+38	798.00	18.3	0.2	79.5		64.1
34+38 to 34+91	53.00	1.2	0.1	5.9		4.3
34+91 to 42+99	808.00	18.5	0.2	48.5	171.0	65.0
42+99 to 47+46	447.00	13.9	0.2	44.5		35.9
47+46 to 48+74	128.00	20.5	0.3			14.5
48+74 to 58+99	1025.00	27.1	0.5	72.6		82.4
58+99 to 61+82	283.00	10.1	0.1	14.6	29.6	22.7
61+82 to 62+52	70.00	12.0	0.2			8.5
62+52 to 66+94	442.00	13.8	0.2	29.5	43.2	35.5
66+94 to 70+33	339.00	7.8	0.1	56.5		27.3
70+33 to 82+87	1254.00	28.7	0.4	154.1		100.8
82+87 to 96+19	1332.00	30.5	0.5	99.8		107.1
96+19 to 111+90	1571.00	35.9	0.5	94.3	187.9	126.3
111+90 to 137+52	2562.00	58.7	0.9	156.5		206.0
137+52 to 146+53	901.00	20.6	0.3	83.4	20.6	72.5
146+53 to 165+00	1847.00	45.9	0.7	186.2		148.5
Subtotals for SouthBound (Right) Lane		427.6	6.4	1371.1	554.7	1333.7
NORTHBOUND (LEFT) LANE						
0+00 to 6+66	666.00	18.9	0.3	33.7		53.6
6+66 to 15+62	896.00	20.5	0.3	61.9		72.0
15+62 to 26+40	1078.00	24.7	0.4	85.0		86.7
26+40 to 34+38	798.00	18.3	0.2	59.5	82.6	64.1
34+38 to 34+91	53.00	1.2	0.1	3.6		4.3
34+91 to 42+99	808.00	18.5	0.2	98.3		65.0
42+99 to 47+46	447.00	13.9	0.2	31.4		35.9
47+46 to 48+74	128.00	20.5	0.3			14.5
48+74 to 58+99	1025.00	27.1	0.5	70.3		82.4
58+99 to 61+82	283.00	10.1	0.1	17.4		22.7
61+82 to 62+52	70.00	12.0	0.2			8.5
62+52 to 66+94	442.00	13.8	0.2	42.1		35.5
66+94 to 70+33	339.00	7.8	0.1	18.7	49.0	27.3
70+33 to 82+87	1254.00	28.7	0.4	61.1	316.2	100.8
82+87 to 96+19	1332.00	30.5	0.5	147.9	3.3	107.1
96+19 to 111+90	1571.00	35.9	0.5	161.0		126.3
111+90 to 137+52	2562.00	58.7	0.9	244.7		206.0
137+52 to 146+53	901.00	20.6	0.3	74.6		72.5
146+53 to 165+00	1847.00	45.9	0.7	157.4		148.5
Subtotals for NorthBound (Left) Lane		427.6	6.4	1368.6	451.1	1333.7
TOTALS		855.2	12.8	2739.7	1005.8	2667.4

NOTE: Quantities shown do not include materials for entrances, side roads, and mailbox turnouts.