

DATE	REVISION	BY

SUMMARY OF QUANTITIES


ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	5,226	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	41	
AR125410	MITL-STAKE MOUNTED	EA.	25	
AR125415	MITL-BASE MOUNTED	EA.	6	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EA.	4	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EA.	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA.	7	
AR125904	REMOVE TAXI GUIDANCE SIGN	EA.	2	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EA.	2	
AR125967	RELOCATE REILS	PAIR	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	6,624	
AR156510	SILT FENCE	L.F.	1,507	
AR156511	DITCH CHECK	EA.	5	
AR156513	SEPARATION FABRIC	S.Y.	9,268	
AR156521	HEADWALL PROTECTION	EA.	2	
AR156540	RIPRAP	S.Y.	23	
AR201610	BITUMINOUS BASE COURSE	TON	1,478	
AR208540	OVERSIZE AGGREGATE	TON	4,217	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	3,065	
AR401610	BITUMINOUS SURFACE COURSE	TON	977	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	175	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	604	
AR602510	BITUMINOUS PRIME COAT	GAL.	2,996	
AR603510	BITUMINOUS TACK COAT	GAL.	856	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	19,920	
AR620912	TEMPORARY MARK & LIGHT	L.S.	1	
AR701518	18" RCP, CLASS IV	L.F.	80	
AR705410	POROUS BACKFILL	C.Y.	311	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	4,090	
AR705630	UNDERDRAIN INSPECTION HOLE	EA.	12	
AR752418	PRECAST REINFORCED CONC. FES 18"	EA.	2	
AR901510	SEEDING	AC.	11	
AR908510	MULCHING	AC.	11	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED STORM WATER POLLUTION PREVENTION PLAN
5	PROPOSED TEMPORARY MARKING AND LIGHTING PLAN
6	PROPOSED TEMPORARY MARKING AND LIGHTING DETAILS
7	PROPOSED CONSTRUCTION PLAN STA. 17+00 TO STA. 21+50
8	PROPOSED CONSTRUCTION PLAN STA. 21+50 TO STA. 38+50
9	PROPOSED PAVEMENT PLAN AND PROFILE STA. 16+00 TO STA. 29+00
10	PROPOSED PAVEMENT PLAN AND PROFILE STA. 29+00 TO STA. 36+19.39
11	PROPOSED DRAINAGE PLAN STA. 16+00 TO STA. 21+50
12	PROPOSED DRAINAGE PLAN STA. 21+50 TO STA. 37+50
13	PROPOSED STAKING PLAN 15+90 TO STA. 21+50
14	PROPOSED STAKING PLAN 21+50 TO STA. 30+00
15	PROPOSED STAKING PLAN 30+00 TO STA. 38+50
16	PROPOSED MARKING PLAN STA. 17+00 TO STA. 33+00
17	PROPOSED MARKING PLAN STA. 33+00 TO STA. 49+00
18	PROPOSED MARKING PLAN STA. 49+00 TO STA. 57+00
19	PROPOSED ELECTRICAL PLAN STA. 16+50 TO STA. 21+50
20	PROPOSED ELECTRICAL PLAN STA. 21+50 TO STA. 38+50
21	PROPOSED ELECTRICAL PLAN STA. 54+50 TO STA. 57+50
22	PROPOSED ELECTRICAL SCHEDULE
23	REIL INSTALLATION DETAILS
24	PROPOSED ELECTRICAL DETAIL
25	PROPOSED ELECTRICAL DETAIL
26	PROPOSED ELECTRICAL NOTES
27	PROPOSED ELECTRICAL NOTES
28	ELECTRICAL LEGEND AND ABBREVIATIONS
29	EXISTING VAULT ELECTRICAL ONE LINE DIAGRAM
30	NEW ELECTRICAL ONE LINE DIAGRAM FOR VAULT
31	AIRFIELD LIGHTING WIRING SCHEMATIC
32	HIGH VOLTAGE WIRING SCHEMATIC
33	CCR GROUND BUS RISER AND GROUNDING DETAILS
34	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 16+25 TO STA. 16+50
35	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 16+90 TO STA. 17+00
36	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 17+17.50 TO STA. 17+35
37	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 17+50 TO STA. 18+00
38	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 18+50 TO STA. 19+00
39	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 19+50 TO STA. 20+00
40	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 20+50 TO STA. 21+00
41	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 21+50 TO STA. 22+00
42	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 22+50 TO STA. 23+00
43	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 23+50 TO STA. 24+00
44	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 24+50 TO STA. 25+00
45	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 25+50 TO STA. 26+00
46	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 26+50 TO STA. 27+00
47	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 27+50 TO STA. 28+00
48	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 28+50 TO STA. 29+00
49	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 29+50 TO STA. 30+00
50	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 30+50 TO STA. 31+00
51	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 31+50 TO STA. 32+00
52	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 32+50 TO STA. 33+00
53	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 33+50 TO STA. 34+00
54	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 34+50 TO STA. 35+00
55	PROPOSED TAXIWAY "A" CROSS-SECTIONS STA. 35+50 TO STA. 36+19.39

CARMi MUNICIPAL AIRPORT
CARMi, ILLINOIS

HEL Project No. 801-077XV-0800
Filename: R-002FLP.DWG
Scale: NOT TO SCALE
Date: 11/14/06



Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

EXTEND PARTIAL
PARALLEL TAXIWAY
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS