

SUMMARY OF QUANTITIES

ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	ENTRANCE ROAD		PARKING LOT	
				FED./STATE/LOCAL		LOCAL	
				BID QUANTITY	FINAL QUANTITY	BID QUANTITY	FINAL QUANTITY
AR106512	TYPE A AREA LGT POLE W/2 FIXTURES	EACH	3				3
AR106521	TYPE B AREA LGT POLE W/1 FIXTURE	EACH	8	8			
AR106531	TYPE C AREA LGT POLE W/1 FIXTURE	EACH	2				2
AR106641	TYPE D ASSEMBLY- 1 FIXTURE	EACH	6	6			
AR106965	RELOCATE LIGHT POLE & FIXTURE	EACH	9	2			7
AR108406	1/C #6 600 V UG CABLE	L.F.	6,480	6,480			
AR108410	1/C #10 600 V UG CABLE	L.F.	12,000	4,000			8,000
AR108800	CONTROL CABLE	L.F.	450				450
AR110201	1" PVC DUCT, DIRECT BURY	L.F.	3,350	1,350			2,000
AR110202	2" PVC DUCT, DIRECT BURY	L.F.	1,000	1,000			
AR110610	ELECTRICAL HANDHOLE	EACH	10	5			5
AR110906	REMOVE ELECTRICAL HANDHOLE	EACH	2	2			
AR150530	TRAFFIC MAINTENANCE	L.S.	1	0.90			0.10
AR151420	CLEARING TREES 0-2.5' BUTT. DIA.	EACH	38	10			28
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	764	364			400
AR152440	BORROW EXCAVATION	C.Y.	30,137	15,408			14,729
AR156500	TEMPORARY EROSION CONTROL	L.S.	1	0.75			0.25
AR156513	SEPARATION FABRIC	S.Y.	23,570	7,802			15,768
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	5,789	1,909			3,880
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	570	570			
AR501506	6" PCC PAVEMENT	S.Y.	15,925				15,925
AR501508	8" PCC PAVEMENT	S.Y.	6,574	6,574			
AR501530	PCC TEST BATCH	EACH	1	0.36			0.64
AR501604	4" PCC SIDEWALK	S.F.	6,482				6,482
AR501690	PCC SIDEWALK REMOVAL	S.F.	2,526				2,526
AR501900	REMOVE PCC PAVEMENT	S.Y.	8,348	7,098			1,250
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	4,562	372			4,190
AR620900	PAVEMENT MARKING REMOVAL	S.F.	438				438
AR701200	SLOTTED DRAIN	L.F.	1,047				1,047
AR701206	6" CMP	L.F.	20	20			
AR701224	24" CMP	L.F.	58				58
AR701412	12" RCP, CLASS III	L.F.	345	277			68
AR701415	15" RCP, CLASS III	L.F.	113	57			56
AR701418	18" RCP, CLASS III	L.F.	20	20			
AR701424	24" RCP, CLASS III	L.F.	628	617			11
AR701430	30" RCP, CLASS III	L.F.	186	186			
AR701436	36" RCP, CLASS III	L.F.	136	136			
AR701900	REMOVE PIPE	L.F.	1,543	1,543			
AR705504	4" PERFORATED UNDERDRAIN	L.F.	3,850	3,850			
AR751411	INLET - TYPE A	EACH	11	9			2
AR751412	INLET - TYPE B	EACH	4	4			
AR751415	INLET - SPECIAL	EACH	1				1
AR751540	MANHOLE 4'	EACH	3				3
AR751550	MANHOLE 5'	EACH	3	3			
AR751900	REMOVE INLET	EACH	21	21			
AR751903	REMOVE MANHOLE	EACH	8	8			
AR751983	RECONSTRUCT MANHOLE	EACH	3				3
AR752206	METAL END SECTION 6"	EACH	1	1			
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	1	1			
AR760506	6" DUCTILE IRON WATER MAIN	L.F.	87	87			
AR760508	8" DUCTILE IRON WATER MAIN	L.F.	80	80			
AR760516	18" DUCTILE IRON WATER MAIN	L.F.	185	185			
AR760800	FIRE HYDRANT	EACH	1	1			
AR760905	REMOVE FIRE HYDRANT	EACH	2	2			
AR801552	6" WATER VALVE	EACH	1	1			
AR801553	8" WATER VALVE	EACH	1	1			
AR801554	16" WATER VALVE	EACH	1	1			
AR801555	ABANDON WATERMAIN	L.S.	1	1			
AR801556	REMOVE GUARD RAIL	L.F.	1,253				1,253
AR801557	REMOVE AND REERECT STEEL PLATE BEAM GUARD RAIL	L.F.	748				748
AR801558	SIGN BRIDGE	EACH	1	1			
AR801559	REMOVE SIGN BRIDGE	EACH	1	1			
AR801560	SITE SIGNS	EACH	31				31
AR801561	RETAINING WALL SIGN	EACH	3				3
AR801562	RETAINING WALL	L.F.	437	437			
AR801563	RECONSTRUCT TELEPHONE VAULT	EACH	1	1			
AR801564	RELOCATE TICKET DISPENSER & GATE ARM	EACH	1				1
AR801565	DETECTOR LOOP, TYPE 1	L.F.	122	122			
AR801566	RELOCATE SIGN BRIDGE LIGHTING	L.S.	1	1			
AR801567	ABANDON STORM SEWER	L.S.	1				1
AR901510	SEEDING	ACRE	1.84	1.42			0.42
AR908510	MULCHING	ACRE	1.84	1.42			0.42
AR910400	GUARD RAIL	L.F.	960	545			415
AR910410	PARKING BLOCK	EACH	12				12
AR910420	BOLLARD	EACH	3				3
AR910976	RELOCATE ROADWAY SIGNS	L.S.	1	1			

IL. PROJ: MLI-3673 AIP PROJ: 3-17-0068-XX

QUAD CITY INTERNATIONAL AIRPORT
Moline, IL



REVISIONS		
NO.	ITEM	DATE

PLOTTING SCALE:	1" = 1'
DRAWN BY:	BLH
CHECKED BY:	SAS
DATE:	APRIL 2007

McClure
Engineering Associates, Inc.
4700 Kennedy Drive East Moline, Illinois 61244
(309) 792-9350 Fax (309) 792-8974
Design Firm License: Illinois 184-000816
Copyright 2007 By McClure Engineering Associates, Inc.

SUMMARY OF QUANTITIES
ENTRANCE ROAD RELOCATION AND PARKING LOT EXPANSION
MOLINE, ILLINOIS
FILE NAME: F:\0107.001\DWG\0700150.DWG
JOB NUMBER: 01-29-07-001

SHEET NO.
2
OF 41