QU004

℄ PROPOSED ENTRANCE ROAD

PROP. RATE SIGN

PROP. EDGE OF PAVEMENT

40 STALLS @ 10' X 18'

10 STALLS @ 10' X 18'

R20'

3' (TYP.)

R5'

24' (MIN.)

PAINTED ISLAND (TYP.)

11 STALLS @ 10' X 18'

13 STALLS @ 10' X 18'

14 STALLS @ 10' X 18'

PROP. WAYFINDING SIGN

PROP. EXIT SIGN(2)

PAINTED ISLAND (TYP)

16 STALLS @ 10' X 18'

4' (TYP.)

5' (TYP.)

PROP. EXIT SIGN(2)

PROP. EXIST SIGN(2)

10'

160'

140'

110'

3' (TYP.)

22 STALLS @ 10' X 18'

R3.25'

6.5'

7.6'

R4'

R3'

R2'

R1'

4 STALLS @ 10' X 18'

7 STALLS @ 10' X 18'

PAVEMENT MARKING REMOVAL (TYP.)

N

0 30' 60'

Scale: 1" = 30'

IL. PROJ: MLI-3673 AIP PROJ: 3-17-0068-XX

QUAD CITY INTERNATIONAL AIRPORT
Moline, IL

REVISIONS		
NO.	ITEM	DATE

PLOTTING SCALE: 1" = 30'
DRAWN BY: ELH
CHECKED BY: SAS
DATE: APRIL 2007

McClure Engineering Associates, Inc.
4700 Kennedy Drive East Moline, Illinois 61244
(309) 792-9350 Fax (309) 792-9974
Design Firm License: Illinois 184-000816
Copyright 2007 By McClure Engineering Associates, Inc.

PAVEMENT MARKING AND SIGNING PLAN

ENTRANCE ROAD RELOCATION AND PARKING LOT EXPANSION — MOLINE, ILLINOIS

FILE NAME: T:\M0107.001\DWG\07001PM.DWG JOB NUMBER: 01-29-07-001

SHEET NO. 17 OF 41