

GUARD POSTS, GATES, SIGNS, AND PARKING SCHEDULE											
LOCATION	STATION	TO STATION	GUARD	GUARD	GUARDRAIL	TUBULAR	TRASH	REM	SIGN	WOOD	TEMP
			POST	POSTS	REMOV	STEEL	RECEPT	RE-ERECT	PANEL	SIGN	
			REMOV	EACH	FT.	GATE	RELOC	EX SIGN	T1	SUPPORT	FENCE
			EACH	EACH		EACH	EACH	EACH	SQ. FT.	FT.	FT.
MAIN ROAD											
LT & RT	10+43.35	11+75.72									
LT	26+00	403+00									415
RT	26+00	30+00									368
RT	26+86.10							1			
LT	27+49.51	30+00									250
LT	27+95.75							1			
LT	30+00	31+00									100
RT	30+00	31+00									100
LT	40+63							1			
RT	41+52.49							1			
LT	47+96							1			
RT	67+94							1			
LT	74+19							1			
RT	85+23	85+32	13	13							
LT	85+70	89+27	28	60							
LT	85+73							2			
RT	86+11	86+89	13	14							
RT	88+29	88+85	4	10							
RT	88+80								6.25	14	
LT	89+27	90+20.6	15	15							
RT	89+30								1.5	14	
RT	125+25.6							1			
RT	127+50							1			
RT	193+00	193+73									73
RT	193+73	199+63									590
LT	194+54.11	194+58.78									
RT	199+63	205+00							6.25	14	537
RT	226+00								1.5	14	
RT	226+40										
ENTRANCE ROAD											
LT	1502+00								1.5	14	
RT	1502+73							1			
LT	1503+00								6.25	14	
SIDE ROADS											
SHADY REST											
LT	301+50.86	301+73									
LAZY "L"											
RT	400+00	403+00									300
RT	410+65	411+24									
CIRCLE "C"											
RT	450+33	451+15									
RT	450+72							1			
LT & RT	453+50.21	454+38.19									
BOAT RAMP 1											
LT	500+89							1			
LT	500+90							1			
LT	517+98.52	517+98.68		2							
LT	518+40	518+51.5		3							
LT	518+55.7	519+54.6	19	19							
LT & RT	518+83	519+08									
LT	519+02							1			
LONELY OAK WEST											
LT	552+75.27					1					
PONDEROSA											
LT	909+60	909+65									
RT	910+65							1.5		10	
RT	910+65							0.5			
LAKE VIEW											
RT	1000+89							1			
FISHING PIER											
RT	1101+85								1.5	10	
RT	1101+85								0.5		
LT	1102+00							1			

GUARD POSTS, GATES, SIGNS, AND PARKING SCHEDULE													
LOCATION	STATION	TO STATION	GUARD	GUARD	GUARDRAIL	TUBULAR	TRASH	REM	SIGN	WOOD	TEMP		
			POST	POSTS	REMOV	STEEL	RECEPT	RE-ERECT	PANEL	SIGN			
			REMOV	EACH	FT.	GATE	RELOC	EX SIGN	T1	SUPPORT	FENCE		
			EACH	EACH		EACH	EACH	EACH	SQ. FT.	FT.	FT.		
LOOKOUT POINT													
LT & RT	1200+61	1202+55											
RT	1200+75	1202+01								234			
POSEN													
LT & RT	1303+95	1304+15							12				
LT & RT	1304+05	1304+10											
PINE PICNIC AREA													
RT & LT	1601+96	1601+99							8				
TOTAL=													
				112.0	136.0	234.0	1.0	1.0	4.0	13.0	27.3	104.0	2333.0

EARTHWORK SCHEDULE					
LOCATION	STATION	TO STATION	TOPSOIL	EARTH	CHANNEL
			FUR & PLACE	EXCAVATION	
			VAR DEPTH	SPECIAL	EXCAVATION
			SQ. YD.	CU YD	CU YD
MAIN ROAD					
LT	10+65.07	10+77.32			4
	11+26.16	11+88.12			24
LT	11+39.40	11+59.90			4
LT	13+22				20
LT	25+41				7
LT	31+10				9
LT	33+64				8
LT	38+00				66
LT	39+40				20
LT	54+48				11
LT	60+24				8
RT	84+48	85+20			5
LT	102+02				11
LT	108+56				14
LT	113+04				17
LT	114+38				13
LT	122+05				61
LT	131+80				6
LT	137+11				48
LT	141+97				40
LT	150+95				14
RT	164+68				13
LT	168+66				22
LT	174+75				113
RT	192+93				16
LT	194+57.32	195+04.83			11
LT	199+03				22
LT	205+90				550
LT	216+23				82
LT	220+56				78
ENTRANCE ROAD					
RT 1505+74					35
SIDE ROADS					
SHADY REST					
RT	300+05.97	300+49	86	4	
RT & LT	300+49	301+21	146	7	
LT	352+08.20	353+25.39		5	
LAZY "L"					
RT	410+64.61	411+24.12		72	
LT	452+94.69	454+39.98	134	22	
RT	453+14.58	453+63.08	76	13	
LT & RT	454+11.99	454+42.60		2	
BOAT RAMP 1					
LT	500+41	501+34	114		
LT	502+94	504+41	300	50	
LT	517+65	518+82	120		
LONELY OAK WEST					
LT	552+83.20	553+20.21		21	
LONELY OAK NORTH					
RT	561+96.95	562+54.05		15	
LT	562+03.7	562+59.9		16	
LT & RT	562+55.7	562+61.74		0.2	

EARTHWORK SCHEDULE					
LOCATION	STATION	TO STATION	TOPSOIL	EARTH	CHANNEL
			FUR & PLACE	EXCAVATION	
			VAR DEPTH	SPECIAL	EXCAVATION
			SQ. YD.	CU YD	CU YD
SITE RESIDENT					
LT	602+49.5	602+78.86			7
LITTLE BEAR NORTH					
LT	750+66.35	750+86.56			15
PONDEROSA					
LT	905+19	905+55			3
LT	906+27	906+33			1
RT	906+29		20		
RT	906+98	908+21			140
LT	907+67	907+78			17
LT	907+70	907+77			3
RT	908+52	909+60			9
LT	909+39	909+96			2
LT & RT	910+52	910+83			8
RT	910+61	910+73			1
LAKE VIEW					
LT	1000+32	1000+47			1
LT	1000+47	1000+74			5
LT & RT	1000+59	1000+95			3
FISHING PIER					
LT	1100+00	1101+29.72	501		111
LT	1101+57.08	1101+91	45		10
LT & RT	1101+57.08	1102+00	126		28
RT	1101+13.5	1102+00	700		183
LOOKOUT POINT					
LT & RT	1201+76	1203+04		106	20
RT	1202+24	1203+04		72	12
SAWMILL					
LT & RT	1405+25	1405+90			29
PINE PICNIC AREA					
RT	1601+67.42	1601+95.95		27	7
LT	1601+73.24	1601+97.89		27	7
TOTAL			2600	1997.3	204.0

FILE NAME =	USER NAME = #USER#	DESIGNED - R.H.D.	REVISED -
#FILE#		DRAWN - S.D.L.	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - R.H.D.	REVISED -
	PLOT DATE = #DATE#	DATE - 4/12/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WASHINGTON COUNTY CONSERVATION AREA
SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 14 OF 112 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		WASHINGTON	112	14
			CONTRACT NO. 46223	
ILLINOIS FED. AID PROJECT				

JOB NO. 250-061-W VASCONCELLES ENGINEERING CORP. DESIGN FIRM REGISTRATION NUMBER 184-002107